STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES																TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
												FULL E&C ITEMS	EROSION CONTROL	LAND-SCAPING	ROADWAY	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
													12				EST	12		LB	SEED-WINTER RYE	651.17			
													1760				5	1760		LB	FERTILIZER	651.18			
														10			.5	10		LB	FERTILIZER (MOD - MYCORRIZAL)	651.18			
													8					8		TON	AGRICULTURAL LIMESTONE	651.20			
													9				1	9		TON	HAYMULCH	651.25			
														7				7		CY	CEDAR BARK MULCH	651.27			
															1900		13	1900		CY	TOPSOIL	651.35			
													1					1		LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10			
													80				EST	80		HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20			
													1					1		LU	FIELD MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I)	652.30			
													6100				87	6100		SY	EROSION MATTING (JUTE)	654.10			
														46			EST	46		EACH	EVERGREEN TREES (THUJA OCCIDENTALIS / EASTERN WHT. CEDAR, 4' - 5' HT)	656.20			
														1				1		EACH	DECIDUOUS TREE (SUGAR MAPLE, ACER SACHARUM, 2-21/2" CALIPER)	656.30			
															77.25			77.25		SF	TRAFFIC SIGNS, TYPE A	675.20			
															224			224		LF	FLANGED CHANNEL SIGN POST	675.301			
															18			18		EACH	REMOVING SIGNS	675.50			
															14			14		EACH	DELINEATORS W/STEEL POSTS	676.10			
															3			3		EACH	REMOVE & RESETTING LIGHT POLE (MOD.- FLAG POLE)	679.25			
															10		EST	10		TON	COLLECTION & DISPOSAL OF BULKY METALLIC WASTE	681.10			

PROJECT NAME: HARDWICK
PROJECT NUMBER: STP ST 030-3(4)

FILE NAME: D04e060qty.dgn
PROJECT MANAGER: A. BOMBARDIER
DESIGNED BY: M. NUTTER
QUANTITY SHEET #3

PLOT DATE: 3/2/05
DRAWN BY: M. NUTTER
CHECKED BY: A. BOMBARDIER
SHEET 6 OF 63