



SL306+41.43 LT65.84  
 REMOVE L.PINE  
 PLANT NEW SUGAR MAPLE  
 2-2 1/2" CALIPER

SL CURVE #2 DATA  
 $\Delta = 5^{\circ}58'19.00''$  LT  
 $D = 2^{\circ}51'53.00''$   
 $R = 2000.00$   
 $T = 104.32$   
 $L = 208.46$   
 $E = 2.72$

307+05 - 307+15 LT  
 NEW 6" X 18" UNDERDRAIN CARRIER PIPE (CREP)  
 WITH PRECAST (MOD.) AND CAST IRON COVER & INLET  
 8' UD CARRIER

18" PIPE AND DIVINSTALLED  
 BY J.P. SICARD BEFORE  
 CONTRACT WAS LET  
 NOVEMBER 05

307+15 - 307+55 LT  
 NEW 6" X 18" UNDERDRAIN CARRIER PIPE  
 CONNECT TO EXISTING 8" UNDERDRAIN  
 PAYMENT FOR CONNECTION REMOVAL  
 EXISTING UNDERDRAIN AND PATCHING  
 IT WILL BE IDENTICAL TO OTHER  
 CONTRACT ITEMS

BM #3  
 TOP OF BOLT AT END  
 OF ARROW ON HYDRANT  
 ELEV. 938.3360

SL CURVE #3 DATA  
 $\Delta = 18^{\circ}04'17.00''$  RT  
 $D = 9^{\circ}42'40.00''$   
 $R = 590.00$   
 $T = 93.82$   
 $L = 186.09$   
 $E = 7.41$

ADDED PAVED DITCH  
 307+45 - 311+00 LT  
 ITEM 616.47

ADDED 4' CHAIN LINK FENCE W/ BRACING ASSEMBLIES  
 SEE COD #3 DATED 9-14-06.

ADDED 4' CHAIN LINK FENCE W/ BRACING ASSEMBLIES  
 SEE COD #3 DATED 9-14-06.

ADDED CEDAR SPLIT RAIL FENCE  
 SEE COD #3 DATED 9-14-06.

YIELDING MARKER POSTS  
 1 EA

LEGEND:

- INCLINOMETER (EXISTING) - INCL (E) O
- INCLINOMETER (NEW) - INCL (N) O (50' EA)
- MONITORING WELL (EXISTING) - MW (E) +
- MONITORING WELL (NEW) - MW (N) + (20' EA)

SL CURVE #4 DATA  
 $\Delta = 4^{\circ}59'58.00''$  LT  
 $D = 4^{\circ}24'27.00''$   
 $R = 1300.00$   
 $T = 56.75$   
 $L = 113.43$   
 $E = 1.24$



PROJECT NAME:	HARDWICK
PROJECT NUMBER:	STP ST 030-3(4)
FILE NAME:	d04e060bdr.dgn
PROJECT LEADER:	A. BOMBARDIER
DESIGNED BY:	M. NUTTER
IPARM NAME:	d04e060k02.t
PLOT DATE:	18-OCT-2005
DRAWN BY:	M. NUTTER
CHECKED BY:	A. BOMBARDIER
SHEET	16 OF 63