| LOCATION | | | CURBED SIDEWALKS | | | | | | DROP INLETS | | | GUARDRAIL | | | | | | | | MISC. | | | | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| STATION | STATION | POS. | 203.15 COMM. EXCAV. | | 301.28 SUBBASE OF CR. GRAV. (FINE) | 616.21 VERTICAL GRANITE CURB | 616.40 REMOVING RESETTING CURB | 618.10 PORT. CEM. CONC. SDWK 5 INCHS | 604.40 CHANGE ELEV. D. I. | 604.412 REHAB. D. I. CLASS I | | 616.31 BIT. CONCRETE CURB | | 621.205 S.B.G.R. GALV. W/ 8' POSTS | | | 621.60 ANCHOR FOR G.R. | | 621.80 REMOVE & DISP. G.R. | | 604.42 CHANGE ELEV. SMH | 616.47 BIT. CONC. GUTTERS & ISLANDS | 629.20 ADJUST ELEV. VALVE BOX | | | | |
| LUDLOW | | | CY | | TON | FT | FT | SY | EA | EA | | TON | | FT | | | EA | | FT | | EA | EA | EA | | | | |
| 113+85 | | RT | 11.8 | | 20.6 | 51.0 | | 26.0 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 113+85 | | LT | 3.7 | | 5.8 | 19.0 | | 5.7 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 5 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 114+25 | | RT | 12.1 | | 18.2 | 88.0 | | 21.9 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 114+28 | | LT | 11.6 | | 17.3 | 44.0 | | 21.4 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 116+62 | | LT | 5.8 | | 8.4 | 19.0 | | 11.4 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 116+62 | | RT | 5.8 | | 8.4 | 19.0 | | 11.4 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 117+57 | | LT | 5.8 | | 8.4 | 19.0 | | 11.4 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 118+17 | | LT | 5.1 | | 7.6 | 19.0 | | 9.7 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 119+24 | | LT | 5.8 | | 8.4 | 19.0 | | 11.4 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 119+24 | | RT | 5.1 | | 7.6 | 19.0 | | 9.7 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 119+59 | | LT | 5.0 | | 7.9 | 24.0 | | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 1W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 119+95 | | LT | 5.0 | | 7.9 | 24.0 | | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 1W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 119+95 | | RT | 5.1 | | 7.6 | 19.0 | | 9.7 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 122+36 | | LT | 5.8 | | 8.4 | 19.0 | | 11.4 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 122+82 | | LT | 5.0 | | 7.9 | 24.0 | | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 1W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 123+28 | | LT | 5.0 | | 7.9 | 24.0 | | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 1W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 124+91 | | LT | 5.1 | | 7.6 | 19.0 | | 9.7 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 125+33 | | LT | 5.8 | | 8.4 | 19.0 | | 11.4 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 125+33 | | RT | 5.8 | | 8.4 | 19.0 | | 11.4 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 6 W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 126+33 | 141+22 | RT | | | | | | | | | | | | | | | | | 1489.0 | | | | | | | |
| 126+33 | 141+20 | RT | | | | | | | | | | 18.9 | | 1627.0 | | | 1.0 | | | | | | | | | ANCHOR @ 141+20 (INSTALL 1- 16' RADIUS PANEL), BITUMINOUS CONCRETE CURB @ 126+60 ~ 140+00 |
| 128+57 | | LT | 5.0 | | 7.9 | 24.0 | | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 1W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 128+79 | | LT | 5.0 | | 7.9 | 24.0 | | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 1W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 138+28 | | LT | 5.0 | | 7.9 | 24.0 | | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 1W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 139+19 | | LT | 5.0 | | 7.9 | 24.0 | | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT LANDING W/DETECTABLE WARNING SURFACE |
| 141+24 | | RT | 1.0 | | 1.1 | | | 2.8 | | | | | | | | | | | | | | | | | | CONSTRUCT CROSSWALK LANDING W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 141+24 | | LT | 5.0 | | 7.9 | | 12.0 | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 1W/DETECTABLE WARNING SURFACE (CAST IRON) |
| 143+74 | 143+83 | LT | 2.5 | | 3.7 | | 9.0 | 4.8 | | | | | | | | | | | | | | | | | | RECONSTRUCT SIDEWALK |
| 144+05 | 144+15 | LT | 2.9 | | 4.2 | | 10.0 | 5.3 | | | | | | | | | | | | | | | | | | RECONSTRUCT SIDEWALK |
| 146+45 | | LT | 5.0 | | 7.9 | 24.0 | | 7.6 | | | | | | | | | | | | | | | | | | CONSTRUCT SIDEWALK RAMP TYPE 1W/DETECTABLE WARNING SURFACE (CAST IRON) |
| SHEET 1 SUBTOTAL | | | 181.4 | | 260.2 | 1063.0 | 143.0 | 350.7 | 54 | 3 | | 0 | | 0 | | | 0 | | 0 | | 24 | 5 | 31 | | | | |
| SHEET 2 SUBTOTAL | | | 156.6 | | 239.1 | 627.0 | 31.0 | 282.5 | 0 | 0 | | 18.9 | | 1627.0 | | | 1 | | 1489.0 | | 0 | 0 | 0 | | | | |
| PROJECT SUBTOTALS | | | 338.0 | | 499.3 | 1690.0 | 174.0 | 633.2 | 54 | 3 | | 18.9 | | 1627.0 | | | 1 | | 1489.0 | | 24 | 5 | 31 | | | | |
| ROUNDING | | | 12.0 | | 50.7 | 20.0 | 1.0 | 6.8 | 0 | 0 | | 1.1 | | 23 | | | 0 | | 11.0 | | 0 | 0 | 0 | | | | |
| PROJECT TOTAL | | | 350.0 | | 550.0 | 1710.0 | 175.0 | 640.0 | 54 | 3 | | 20.0 | | 1650 | | | 1 | | 1500.0 | | 24 | 5 | 31 | | | | |

**ITEM DETAIL SHEET 2**

SURVEYED BY CLD DATE 1/05
DRAWN BY MRS DATE 11/05
SQUAD LEADER PTS
DESIGN FILE NO. /pave/05B008/pb008.dgn
IPARM FILE pb008id02.i DATE PLOTTED 20-MAY-2010 14:3
PROJ. NAME: LUDLOW
PROJ. NO.: NH2409(1)S
SHEET 11 OF 51 SHEETS