STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #11

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																							
STA 125+85 LT		1	30	30	6.25						1			X 13		X		X																	E-152
		1	24	12	2.00																														E-152
STA 126+63 LT		1	12	18	1.50						1			X 12		X		X															R7-1		
		1	12	6	0.50																												R7-201		
STA 126+72 RT		1	6	10	0.42						1		~~X~~	8	X			X																E-138
STA 127+00 RT		1	24	30	5.00						1			X 14		X		X																E-142
STA 127+12 RT		1	12	18	1.50						1			X 13		X		X															R7-1		
		1	12	6	0.50																												R7-201		
STA 128+50 LT	BOWKER CT	1	36	9	2.25						1			X 13		X		X															SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		E-123
		1 1	30 6	30 10	6.25 0.42																											BACK TO BACK		E-143 E-138
STA 129+73 LT		1	12	18	1.50						1			X 12		X		X															R7-1		
		1	12	6	0.50																												R7-201		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAYTRAFFIC & SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TOTALS	SF 28.59	SF	EA.	SF	FT ~~105~~ 85	FT ~~105~~	EA	LB	EA.	LB	EA.	EA.	LB
					FT ~~15~~ ~~90~~	FT ~~15~~ ~~90~~ FT		LB LB LB		LB LB LB LB			

TRAFFIC SIGN SUMMARY SHEET #11

PROJECT NAME: LUDLOW
PROJECT NUMBER: NH 2409(1)S

FILE NAME: /pave/05B008/pb008.dgn
PROJECT LEADER: PTS
DESIGNED BY: NLL
PARM. FILE NAME: pb008tsll.i
PLOT DATE: 20-MAY-2010 14:3
DRAWN BY: MRS
CHECKED BY: NLL
SHEET 43 OF 51