STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																				REMARKS	SIGN DETAIL	
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			FOUNDATION	TUBULAR STEEL Ø (in) lb/ft				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															1.75	2.0	2.5			3.0	4.0	4.0 MOD		3.0	3.5	4.0	5.0	24"	30"						
												1.12	2.0	3.0	1.88	2.16	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
											OPTION ITEMS																								
KILLINGTON: 401+28.0, LT	R-1 0040 1121 0760	1	6	10	0.42						1	X		7.5'	X			X														SIGN ID CODE VD-700		E-138
405+84.0, LT	R-1	1	30	30	6.25						1			14.0' X		X		X														SIGN ID CODE W2-2M		E-155
409+40.0, LT	R-1 WATCH FOR TURNING VEHICLES	1	36	36	9.00						2			28.0' X																		SIGN TO BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE VW-205		E-154
411+84.0, RT	0040 1121 0780	1	6	10	0.42						1	X		8.1'	X			X														SIGN ID CODE VD-700		E-138
424+57.0, LT	R-3 JOHNSON RD						1				1			13.0' X		X		X														SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1121 0805	1 1	30 6	30 10	6.25 0.42																										BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
425+11.0, LT	R-1 LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			13.0' X		X		X														SIGN ID CODE VR-017		E-141
428+03.0, RT	R-2 LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			13.4' X		X		X														SIGN ID CODE VR-017		E-141
												LF	LF	LF	LF	LF	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
												28.0		~~56.0~~ (28.0) 97.0	28.0	56.0																			
TOTALS		SF	SF	EA.	SF							LF			LF					LB			EA.	LB				EA.	EA.	LB					
		32.76		1								~~84.0~~ (28.0) 97.0			84.0																				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT NAME: KILLINGTON - BRIDGEWATER
PROJECT NUMBER: NH 2502(I)S

FILE NAME: p05b036.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05b036tss01.i

PLOT DATE: 15-MAY-2008 14
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 38 OF 74