STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
KILLINGTON: 428+42.0, RT	R-2 WARDELL RD						1				1			13.0′ X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1121 0811	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
432+96.0, RT	0040 1121 0820	1	6	10	0.42						1	X		8.0′	X			X															SIGN ID CODE VD-700		E-138
434+43.0, RT	R-1 WEST BRIDGEWATER BRIDGEWATER CORS. 4	1	30	18	3.75						1			13.0′ X		X		X																	E-128A
435+14.0, LT	R-3 JOHNSON RD						1				1			12.5′ X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1121 0825	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
435+57.0, LT	R-1 LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			14.0′ X		X		X															SIGN ID CODE VR-017		E-141
435+99.0, RT	R-2	1	12	36	3.00						1			11.5′ X		X		X															SIGN ID CODE OM-3R		E-120
	BRIDGE 34 US 4	1	6	8	0.33																											SIGN ID CODE VD-701		E-134
436+56.0, LT	R-1	1	12	36	3.00						1			11.0′ X		X		X															SIGN ID CODE OM-3L		E-120
												LF 14.0	LF	LF ~~84.0~~ 83.0	LF 14.0	LF 84.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 28.84	SF	EA. 2	SF							LF ~~98.0~~ 83.0			LF 98.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: KILLINGTON - BRIDGEWATER
PROJECT NUMBER: NH 2502(I)S

FILE NAME: p05b036.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05b036tss02.i
PLOT DATE: 15-MAY-2008 14
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 39 OF 74