STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAMEMENT REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																						
KILLINGTON: 438+10.0, RT	R-1	1	12	36	3.00						1			11.0' X		X		X						7.6	9.0	10.8	14.6						SIGN ID CODE OM-3L		E-120
438+19.0, RT	R-1 LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			13.0' X		X		X															SIGN ID CODE VR-017		E-141
438+67.0, LT	R-2	1	12	36	3.00						1			11.5' X		X		X															SIGN ID CODE OM-3R		E-120
	BRIDGE 34 US 4	1	6	8	0.33																												SIGN ID CODE VD-701		E-134
438+72.0, RT	R-2 HADLEY HILL RD						1				1			13.0' X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1121 0831	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
440+54.0, RT	R-2	1	36	36	9.00						2			16.0' X																			SIGN TO BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE WI-2Mc L	62	
	40 M.P.H.	1	24	24	4.00																												SIGN ID CODE WI3-1		E-155
443+50.0, RT	WATCH FOR TURNING VEHICLES	1	36	36	9.00						2			13.0' X																			SIGN TO BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE VW-205		E-154
443+52.0, LT	0040 1121 0840	1	6	10	0.42						1	X		8.0'	X			X															SIGN ID CODE VD-700		E-138
												LF 14.0	LF	LF ~~56.0~~ (56.0) 85.5	LF 14.0	LF 56.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 40.42	SF	EA. 1	SF							LF ~~70.0~~ 85.5 (~~56.0~~)			LF 70.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #3

PROJECT NAME: KILLINGTON - BRIDGEWATER
PROJECT NUMBER: NH 2502(I)S

FILE NAME: p05b036.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05b036tss03.i

PLOT DATE: 15-MAY-2008 14
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 40 OF 74