STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
BRIDGEWATER: 5+65.0, LT	SOUTH WEST NORTH	1 1 1	24 24 24	12 12 12	2.00 2.00 2.00						2												2	194.0 ~~180.0~~								X	SIGN ID CODE M3-3 SIGN ID CODE M3-4 SIGN ID CODE M3-1		E-136B E-136A E-136B
R-9	VERMONT 100 4 VERMONT 100	1 1 1	30 24 30	24 24 24	5.00 4.00 5.00																												SIGN ID CODE M1-5 SIGN ID CODE M1-4 SIGN ID CODE M1-5		E-136B E-136A E-136B
	← ↑ ↑	1 1 1	21 21 21	15 15 15	2.19 2.19 2.19																												SIGN ID CODE M6-1 SIGN ID CODE M6-3 SIGN ID CODE M6-3		E-136B E-136A E-136B
5+74.0, LT	R-3 CRAM RD						1				1			13.0' X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1405 0011	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
6+17.0, RT	EAST	1	24	12	2.00						1			14.0' X		X		X															SIGN ID CODE M3-2		E-136A
	4	1	24	24	4.00																												SIGN ID CODE M1-4		E-136A
6+22.0, LT	R-1 LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			13.0' X		X		X															SIGN ID CODE VR-017		E-141
7+65.0, LT	R-4 ↑ KILLINGTON 6	1	72	12	6.00						2			32.0' X 16+16		X		X															SIGN ID CODE D1-1		E-123
	↑ RUTLAND 17	1	72	12	6.00																												SIGN ID CODE D1-1		E-123
	← PLYMOUTH UNION 6	1	72	12	6.00																												SIGN ID CODE D1-1		E-123
	← LUDLOW 16	1	72	12	6.00																												SIGN ID CODE D1-1		E-123
												LF	LF	LF ~~70.0~~ 72.0	LF	LF 70.0	LF		EA.	LB	LB	LB		LB 194 ~~180.0~~	LB	LB	LB								
	TOTALS		SF 68.24	SF	EA. 1	SF						LF ~~70.0~~ 72.0			LF 70.0					LB			EA. 2	LB 180.0				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #6

PROJECT NAME: KILLINGTON - BRIDGEWATER
PROJECT NUMBER: NH 2502(1)S

FILE NAME: p05b036.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05b036tss06.i

PLOT DATE: 15-MAY-2008 14
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 43 OF 74