STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
BRIDGEWATER: 128+25.0, RT	R-1 SCHOOL BUS STOP AHEAD	1	36	36	9.00						2			30.0' X 15+15																			SIGN TO BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE S3-1		E-153
130+25.0, RT		1	30	30	6.25						1			16.0' X		X		X															SIGN ID CODE W2-2M		E-155
133+35.0, RT	BRIDGE 41 US 4	1	6	8	0.33						1	X		9.0'	X			X															SIGN ID CODE VD-701		E-134
133+50.0, LT	BRIDGE 41 US 4	1	6	8	0.33						1	X		9.0	X			X															SIGN ID CODE VD-701		E-134
134+10.0, RT	R-1 LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			13.0' X		X		X															SIGN ID CODE VR-017		E-141
134+59.0, RT	R-1 PEARSON RD TH 68						1				1			13.0' X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP / 0040 1405 0254	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
135+50.0, RT	EAST	1	24	12	2.00						1			16.0' X		X		X															SIGN ID CODE M3-2		E-136A
	4	1	24	24	4.00																												SIGN ID CODE M1-4		E-136A
												LF 28.0	LF	LF ~~56.0~~ ~~(28.0)~~ 106.0	LF 28.0	LF 56.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
	TOTALS		SF 33.58	SF	EA. 1	SF						LF ~~84.0~~ ~~(28.0)~~ 106.0			LF 84.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #13

PROJECT NAME: KILLINGTON - BRIDGEWATER
PROJECT NUMBER: NH 2502(1)S

FILE NAME: p05b036.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05b036tss13.i

PLOT DATE: 15-MAY-2008 14
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 50 OF 74