STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 14

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (in) | HEIGHT (in) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | EXIST POST SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | 2.0 | 3.0 | SQUARE STEEL (in) 1.75 lb/ft 1.88 | 2.0 lb/ft 2.16 | 2.5 lb/ft 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3 | 4.0 lb/ft 1.7 | 4.0 MOD lb/ft 1.7 | TUBULAR STEEL Ø (in) FOUNDATION | 3.0 lb/ft 7.6 | 3.5 lb/ft 9.0 | 4.0 lb/ft 10.8 | 5.0 lb/ft 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON DWG. NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | | | OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | | |
| BRIDGEWATER: 135+50.0, LT | WEST | 1 | 24 | 12 | 2.00 | | | | | | 1 | | | 14.0′ X | | X | | X | | | | | | | | | | | | | | | | | SIGN ID CODE M3-4 | | E-136A |
| | 4 | 1 | 24 | 24 | 4.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE MI-4 | | E-136A |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 137+28.0, RT | 0040 1405 0260 | 1 | 6 | 10 | 0.42 | | | | | | 1 | X | | 8.0′ | X | | | X | | | | | | | | | | | | | | | | | SIGN ID CODE VD-700 | | E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 139+50.0, LT | | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | 14.0′ X | | X | | X | | | | | | | | | | | | | | | | | SIGN ID CODE W2-2M | | E-155 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 147+48.0, RT | R-1 SCHOOL BUS STOP AHEAD | 1 | 36 | 36 | 9.00 | | | | | | 2 | | | 28.0′ X 14+14 | | | | | | | | | | | | | | | | | | | | | SIGN TO BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE S3-1 | | E-153 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 147+84.0, LT | 0040 1405 0280 | 1 | 6 | 10 | 0.42 | | | | | | 1 | X | | 8.0′ | X | | | X | | | | | | | | | | | | | | | | | SIGN ID CODE VD-700 | | E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 149+59.0, LT | R-1 | 1 | 12 | 36 | 3.00 | | | | | | 1 | | | 11.0′ X | | X | | X | | | | | | | | | | | | | | | | | SIGN ID CODE OM-3L | | E-120 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 150+15.0, RT | R-1 | 1 | 12 | 36 | 3.00 | | | | | | 1 | | | 11.5′ X | | X | | X | | | | | | | | | | | | | | | | | SIGN ID CODE OM-3R | | E-120 |
| | BRIDGE 42 US 4 | 1 | 6 | 8 | 0.33 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE VD-701 | | E-134 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | LF 28.0 | LF | LF ~~56.0~~ (28.0) 94.5 | LF 28.0 | LF 56.0 | LF | | EA. | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| **TOTALS** | | SF 28.42 | SF | EA. | SF | | | | | | | LF ~~84.0~~ (28.0) 94.5 | | | LF 84.0 | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

**TRAFFIC SIGN SUMMARY SHEET #14**

PROJECT NAME: KILLINGTON - BRIDGEWATER
PROJECT NUMBER: NH 2502(I)S

FILE NAME: p05b036.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05b036tss14.i

PLOT DATE: 15-MAY-2008 14
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 51 OF 74