STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																					
BRIDGEWATER: 151+54.0, LT	R-1	1	12	36	3.00						1			11.5' X		X		X															SIGN ID CODE OM-3R		E-120
	BRIDGE 42 US 4	1	6	8	0.33																												SIGN ID CODE VD-701		E-134
151+78.0, RT	R-1	1	12	36	3.00						1			11.0' X		X		X															SIGN ID CODE OM-3L		E-120
158+40.0, RT	0040 1405 0300	1	6	10	0.42						1	X		12.0'	X			X															SIGN ID CODE VD-700		E-138
159+10.0, RT	BRIDGE 43 US 4	1	6	8	0.33						1	X		9.0'	X																		SIGN ID CODE VD-701		E-134
159+15.0, LT	BRIDGE 43 US 4	1	6	8	0.33						1	X		9.0'	X																		SIGN ID CODE VD-701		E-134
168+96.0, LT	R-1 0040 1405 0320	1	6	10	0.42						1	X		9.0'	X			X															SIGN ID CODE VD-700		E-138
175+27.0, RT	R-1 LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			14.0' X		X		X															SIGN ID CODE VR-017		E-141
175+70.0, RT	R-3 GUNDERSON RD TH 70						1																										SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1405 0333	1 1	30 6	30 10	6.25 0.42						1			13.0' X		X		X															BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
												LF 56.0	LF	LF ~~56.0~~ 88.5	LF 56.0	LF 56.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB							
	TOTALS		SF 19.50	SF	EA. 1	SF						LF ~~112.0~~ 88.5			LF 112.0					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #15

PROJECT NAME: KILLINGTON - BRIDGEWATER
PROJECT NUMBER: NH 2502(1)S

FILE NAME: p05b036.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05b036tss15.i

PLOT DATE: 15-MAY-2008 14
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 52 OF 74