STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 19

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAMES REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
BRIDGEWATER: 283+76.0, LT	R-1	1	12	36	3.00						1			11.5' X		X		X																SIGN ID CODE OM-3R		E-120
	BRIDGE 45 US 4	1	6	8	0.33																												SIGN ID CODE VD-701		E-134
283+93.0, RT	R-1	1	12	36	3.00						1			11.0' X		X		X																SIGN ID CODE OM-3L		E-120
285+47.0, RT	R-1 SPEED LIMIT 40	1	36	36	9.00						2			32.0' X 16+16																				SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE W3-5	62	
287+54.0, LT	BRIDGEWATER CENTER RD						1				1			14.0' X		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	R-2 STOP 0040 1405 0545	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
287+83.0, RT	R-1 BRIDGEWATER CORNERS WOODSTOCK 8	1	30	18	3.75						1			14.0' X		X		X																		E-128A E-128B
288+12.0, LT	R-1 LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			14.0 X		X		X																SIGN ID CODE VR-017		E-141
290+30.0, LT	W BRIDGEWATER 6	1	72	12	6.00						2			28.0' X 14+14		X		X																SIGN ID CODE DI-1		E-123
R-2	RUTLAND 23	1	72	12	6.00																												SIGN ID CODE DI-1		E-123
												LF	LF	LF ~~98.0~~ (28.0) 124.5	LF	LF 98.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 42.75	SF	EA. 1	SF							LF ~~98.0~~ (28.0) 124.5			LF 98.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #19

PROJECT NAME: KILLINGTON - BRIDGEWATER
PROJECT NUMBER: NH 2502(I)S

FILE NAME: p05b036.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05b036tss19.i
PLOT DATE: 15-MAY-2008 14
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 56 OF 74