STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 20

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (in) | HEIGHT (in) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | 2.0 | 3.0 | SQUARE STEEL (in) lb/ft 1.75 1.88 | 2.0 2.16 | 2.5 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3 | 4.0 1.7 | 4.0 MOD 1.7 | TUBULAR STEEL Ø (in) FOUNDATION | lb/ft 3.0 7.6 | 3.5 9.0 | 4.0 10.8 | 5.0 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGN FRAMES REQUIRED | REMARKS | SIGN DETAIL DETAIL ON DWG. NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | | | OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | |
| BRIDGEWATER: 290+76.0, RT | R-2 JCT | 1 | 21 | 15 | 2.19 | | | | | | 1 | | | 14.0' X | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE M2-1 | | E-136B |
| | VERMONT 100A | 1 | 30 | 24 | 5.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE MI-5 | | E-136B |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 293+85.0, LT | R-1 SPEED LIMIT 50 | 1 | 24 | 30 | 5.00 | | | | | | 1 | | | 14.0' X | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE R2-1 | | E-142 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 293+85.0, RT | R-1 SPEED LIMIT 40 | 1 | 24 | 30 | 5.00 | | | | | | 1 | | | 14.0' X | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE R2-1 | | E-142 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 295+68.0, RT | WOODSTOCK 8 | 1 | 72 | 12 | 6.00 | | | | | | 2 | | | 32.0' X 16+16 | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE DI-1 | | E-123 |
| R-3 | WHITE RIVER JCT 22 | 1 | 72 | 12 | 6.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE DI-1 | | E-123 |
| | PLYMOUTH 6 | 1 | 72 | 12 | 6.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE DI-1 | | E-123 |
| | PLYMOUTH UNION 7 | 1 | 72 | 12 | 6.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE DI-1 | | E-123 |
| | 0040 1405 0560 | 1 | 6 | 10 | 0.42 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE VD-700 | | E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 296+18.0, LT | R-2 WEST | 1 | 24 | 12 | 2.00 | | | | | | 1 | | | 14.0' X | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE M3-4 | | E-136A |
| | 4 | 1 | 24 | 24 | 4.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE MI-4 | | E-136A |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | LF | LF | LF ~~84.0~~ 88.0 | LF | LF 84.0 | LF | | EA. | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| | **TOTALS** | SF 47.61 | SF | EA. | SF | | | | | | | LF ~~84.0~~ 88.0 | | | LF 84.0 | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

**TRAFFIC SIGN SUMMARY SHEET #20**

PROJECT NAME: KILLINGTON - BRIDGEWATER
PROJECT NUMBER: NH 2502(I)S

FILE NAME: p05b036.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05b036tss20.i
PLOT DATE: 15-MAY-2008 14
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 57 OF 74