646.402 DURABLE 4 INCH WHITE LINE, THERMOPLASTIC
(ALL LINES WILL INCLUDE EDGE LINE BREAKS AND RADIUS FOR TOWN HIGHWAYS)

FERRISBURGH:
STA 3+00.00- STA 6+95.00 DOTTED LANE LINE RT
STA 3+00.00 - STA 11+75.00 DASHED LANE LINE LT
STA 3+00.00 - STA 19+00.00 EDGE LINE LT & RT
STA 6+95.00 - STA 12+65.00 SOLID LANE LINE RT

646.602 TEMPORARY 4 INCH WHITE LINE, PAINT
(ALL LINES WILL INCLUDE EDGE LINE BREAKS AND RADIUS FOR TOWN HIGHWAYS)

FERRISBURGH:
STA 3+00.00 - STA 6+95.00 DOTTED LANE LINE RT
STA 3+00.00 - STA 11+75.00 DASHED LANE LINE LT
STA 3+00.00 - STA 19+00.00 EDGE LINE LT & RT
STA 6+95.00 - STA 12+65.00 SOLID LANE LINE RT

646.412 DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC
(ALL LINES WILL INCLUDE C/L BREAKS FOR TOWN HIGHWAYS) S=SOLID, D=DASHED

FERRISBURGH:
STA 3+00.00 - STA 12+50.00 SOLID MEDIAN EDGE LINE LT & RT
STA 12+93.60 DOUBLE SOLID LT, NSH-FSH
STA 13+25.00 - STA 16+25.00 SOLID MEDIAN EDGE LINE LT
STA 13+25.00 - STA 16+90.00 SOLID MEDIAN EDGE LINE RT
STA 16+25.00 - STA 19+00.00 DOUBLE SOLID MEDIAN LINE LT
STA 16+90.00 - STA 19+00.00 DOUBLE SOLID MEDIAN LINE RT

646.612 TEMPORARY 4 INCH YELLOW LINE, PAINT
(ALL LINES WILL INCLUDE C/L BREAKS FOR TOWN HIGHWAYS) S=SOLID, D=DASHED

FERRISBURGH:
STA 3+00.00 - STA 12+50.00 SOLID MEDIAN EDGE LINE LT & RT
STA 12+93.60 DOUBLE SOLID LT, NSH-FSH
STA 13+25.00 - STA 16+25.00 SOLID MEDIAN EDGE LINE LT
STA 13+25.00 - STA 16+90.00 SOLID MEDIAN EDGE LINE RT
STA 16+25.00 - STA 19+00.00 DOUBLE SOLID MEDIAN LINE LT
STA 16+90.00 - STA 19+00.00 DOUBLE SOLID MEDIAN LINE RT

646.492 DURABLE LETTER OR SYMBOL, THERMOPLASTIC

FERRISBURGH:
STA 6+99.30 RT, ARROW (1EA)
STA 7+89.80 RT, "O,N,L,Y" (4 EA)
STA 8+80.30 RT, ARROW (1EA)
STA 9+70.80 RT "O,N,L,Y" (4 EA)
STA 10+61.30 RT, ARROW (1EA)
STA 11+51.80 RT, "O,N,L,Y" (4 EA)
STA 12+42.30 RT, ARROW (1EA)
STA 12+93.60 LT, NSH-FSH "S,T,O,P" (4 EA)

646.452 DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC

FERRISBURGH:
STA 16+25.00 - STA 19+00.00 HATCH MEDIAN LT
STA 16+90.00 - STA 19+00.00 HATCH MEDIAN RT

646.692 TEMPORARY LETTER OR SYMBOL, PAINT

FERRISBURGH:
STA 6+99.30 RT, ARROW (2 EA)
STA 8+80.30 RT, ARROW (2 EA)
STA 10+61.30 RT, ARROW (2 EA)
STA 12+42.30 RT, ARROW (2 EA)
STA 12+93.60 LT, NSH-FSH "S,T,O,P" (8 EA)

SEE 49-A

SEE SHEET 49A FOR FERRISBURGH STATE HIGHWAY INTERSECTION DETAIL SHEET

646.482 DURABLE 24 INCH STOP BAR, THERMOPLASTIC

FERRISBURGH:
STA 12+93.60 LT, NSH-FSH

646.682 TEMPORARY 24 INCH STOP BAR, PAINT

FERRISBURGH:
STA 12+93.60 LT, NSH-FSH

646.81 PAINTED CURB

FERRISBURGH:
STA 4+30.00 - STA 12+50.00 RT (820.0 LF)
STA 4+60.00 - STA 12+50.00 LT (790.0 LF)
STA 13+20.00 - STA 13+50.00 LT & RT (71.0 LF)
STA 16+60.00 - STA 16+90.00 LT & RT (62.0 LF)

675.50 REMOVING SIGNS

AS SHOWN - 41

675.60 ERECTING SALVAGED SIGNS

AS SHOWN - 1

STA 5+11.0, LT
DROP INLET TO REMAIN

STA 5+50.0, LT
STA 5+50.0, LT
STA 9+75.0, LT
STA 11+81.0, LT
STA 12+58.0, LT
STA 12+58.0, LT
STA 10+06.0, LT
STA 11+75.0, LT
STA 7+75.0, LT
STA 7+98.0, LT
STA 8+15.0, LT
DROP INLET ALONG MEDIAN
STA 13+30.0, LT
STA 13+65.0, LT
STA 13+65.0, LT
STA 15+95.0, LT
STA 16+75.0, LT
STA 18+94.0, LT
STA 18+94.0, LT
STA 17+00.00
END COLD PLANE & PAVE RESUME OVERLAY
#58
EXISTING 48" CMP
SEE NOTE 2
(FSH) MM 0.245/ STA 12+93.60 (ASPHALT)

STA 6+95.0, RT
STA 7+52.0, RT
STA 10+56.0, RT
STA 12+44.0, RT
STA 11+20.0, RT
STA 12+22.0, LT
DROP INLET ALONG MEDIAN
STA 12+45.0, CL
STA 12+45.0, CL
STA 12+56.0, RT
STA 13+30.0, CL
STA 13+30.0, CL
STA 13+00.0, RT
STA 13+00.0, RT
STA 16+86.0, RT
STA 16+86.0, CL
STA 16+86.0, CL
13+73.0, RT
STA 14+90.0, RT
STA 13+25.00
STA 14+00.00
STA 16+25.00 BEGIN MEDIAN TAPER BEGIN RT SHOULDER WIDENING

BEGIN LT TURN LANE STA 6+95.00

EDGE OF SHOULDER
EDGE OF TRAVELWAY
GRASSED MEDIAN
EDGE OF TRAVELWAY
EDGE OF SHOULDER
U.S. ROUTE 7
SOUTHBOUND
NORTHBOUND
CONCRETE MEDIAN
GRASSED MEDIAN
DI

MATCH LINE STA 3+00, SEE PREVIOUS SHEET
MATCH LINE STA 19+00, SEE NEXT SHEET

604.412 REHAB. DROP INLETS, CATCH BASINS OR MANHOLES, CLASS I

FERRISBURGH:
STA 8+15.0 LT
STA 12+22.0 LT

621.20 STEEL BEAM GUARDRAIL, GALVANIZED

FERRISBURGH:
STA 13+15.0 - STA 16+52.5 LT (387.5 LF)

621.50 MANUFACTURED TERMINAL SECTION, FLARED

FERRISBURGH:
STA 16+52.5 - STA 16+90.0 LT

621.60 ANCHOR FOR STEEL BEAM RAIL

FERRISBURGH:
STA 13+15.0 LT
STA 13+31.0 LT

621.80 REMOVAL AND DISPOSAL OF GUARDRAIL

FERRISBURGH:
STA 13+15.0 - STA 16+79.0 LT (414.0 LF)

676.10 DELINEATOR WITH STEEL POST

TYPE I WHITE

FERRISBURGH:
STA 16+90.0 LT

NOTES:

1. PAVING LIMIT ON ALL TOWN HIGHWAYS SHALL BE MEASURED 25 FT BACK FROM U.S. ROUTE 7 EDGE OF SHOULDER UNLESS DENOTED OTHERWISE ON THE PLANS OR AS DIRECTED BY THE RESIDENT ENGINEER.

2. REMOVE EXISTING GUARDRAIL AND GUARDRAIL END SECTION AND INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AND GUARDRAIL AS DIRECTED BY THE RESIDENT ENGINEER. THE CONTRACTOR SHALL CONNECT TO EXISTING RAIL ALONG NSH-FSH BY INSTALLING A NEW 16' RADIUS PANEL WITH ANCHORS AT EACH END AS DIRECTED BY THE RESIDENT ENGINEER.

SIGN LEGEND
R = REMOVE
S = SALVAGE
N = NEW
RET = RETAIN
B-B = BACK TO BACK
EXISTING = --------
NEW = ————

AREA TO BE COLD PLANED AND PAVED

NOT TO SCALE

PROJECT LAYOUT SHEET #12

PROJECT NAME: NEW HAVEN - FERRISBURGH
PROJECT NUMBER: NH 2503(I)S

FILE NAME: 05b038.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b038ll2.i
PLOT DATE: 31-JUL-2009 15
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 25 OF 87