STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 20

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																		REMARKS	SIGN DETAIL	
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			TUBULAR STEEL Ø (in)					W-SHAPE STEEL				SIGN FRAME REQUIRED		DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															1.75	2.0	2.5			3.0	4.0	4.0 MOD	FOUND-ATION	3.0	3.5	4.0	5.0	FTG. SIZE 24"	FTG. SIZE 30"	WEIGHT	POST SIZE				
												1.12	2.0	3.0	1.88	2.16	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
											OPTION ITEMS																								
FERRISBURGH: 228+48.0, RT	GREENBUSH RD / ROBINSON RD	1	66	24	11.00																											SIGN TO BE MOUNTED ON EXISTING POSTS.	80	
230+94.0, RT	SCHOOL BUS STOP AHEAD	1	30	30	6.25						1			X		X		X														SIGN ID CODE S3-1		E-153
232+32.0, RT	0070 0105 0440	1	6	10	0.42						1	X			X			X														SIGN ID CODE VD-700		E-138
236+02.0, LT	CHAMPLAIN BIKEWAY	1	12	18	1.50						1			X		X		X														SIGN ID CODE VD-503		E-131B
239+60.0, RT	NO OUTLET	1	30	30	6.25						1			X		X		X														SIGN ID CODE W14-2	81	
240+05.0, RT	ROBINSON RD						1				1			X		X		X														SALVAGED SIGN TO BE MOUNTED ON NEW POST, TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0070 0105 0454	1	6	10	0.42		1																								BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700	-	- E-138
240+39.0, LT	GREENBUSH RD						1				1			X		X		X														SALVAGED SIGN TO BE MOUNTED ON NEW POST, TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0070 0105 0454	1	6	10	0.42		1																								BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700	-	- E-138
247+55.0, LT	ROBINSON RD / GREENBUSH RD	1	66	24	11.00																											SIGN TO BE MOUNTED ON EXISTING POSTS.	80	
												FT 14	FT	FT 70	FT 14	FT 70	FT		EA	LB	LB	LB		LB	LB	LB	LB							
TOTALS		SF 37.26	SF	EA. 4	SF							FT 84			FT 84					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #20

PROJECT NAME: NEW_HAVEN_-_FERRISBURGH
PROJECT NUMBER: NH_2503(I)S_____

FILE NAME: 05b038.dgn_____
PROJECT LEADER: D.E.G._____
DESIGNED BY: M.J.M._____
IPARM FILE: p05b038tss20.I

PLOT DATE: 31-JUL-2009 15:54
DRAWN BY: C.A.K._____
CHECKED BY: D.E.G._____
SHEET 71 OF 87