STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 28

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																				REMARKS	SIGN DETAIL	
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			TUBULAR STEEL Ø (in) lb/ft					W-SHAPE STEEL FTG. SIZE				SIGN FRAMES REQUIRED		DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															1.75	2.0	2.5			3.0	4.0	4.0 MOD	FOUND-ATION	3.0	3.5	4.0	5.0	24"	30"	WEIGHT	POST SIZE			
												1.12	2.0	3.0	1.88	2.16	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6							
											OPTION ITEMS																								
	SHEET 52 SUBTOTAL				-		-					56		56	56	56			-				-	-										
	SHEET 53 SUBTOTAL				-		-					70		14	70	14			-				-	-										
	SHEET 54 SUBTOTAL				-		-					14		70	14	70			-				-	-										
	SHEET 55 SUBTOTAL				-		-					56		14	56	14			-				-	-										
	SHEET 56 SUBTOTAL				-		-					-		98	-	98			-				-	-										
	SHEET 57 SUBTOTAL				-		-					-		42	-	42			1				-	-										
	SHEET 58 SUBTOTAL				-		-					-		56	-	56			-				-	-										
	SHEET 59 SUBTOTAL				-		-					14		28	14	28			-				-	-										
	SHEET 60 SUBTOTAL				-		-					-		56	-	56			-				-	-										
	SHEET 61 SUBTOTAL				-		-					28		-	28	-			-				-	-										
	SHEET 62 SUBTOTAL				-		-					14		42	14	42			-				-	-										
	SHEET 63 SUBTOTAL				-		-					-		70	-	70			-				-	-										
	SHEET 64 SUBTOTAL				-		-					-		70	-	70			-				-	-										
	SHEET 65 SUBTOTAL				-		-					14		42	14	42			-				-	-										
	SHEET 66 SUBTOTAL				-		-					28		70	28	70			-				-	-										
	SHEET 67 SUBTOTAL				-		-					14		84	14	84			-				-	-										
	SHEET 68 SUBTOTAL				-		-					14		70	14	70			-				-	-										
	SHEET 69 SUBTOTAL				-		-					28		70	28	70			-				-	-										
	SHEET 70 SUBTOTAL				-		-					56		42	56	42			-				-	-										
	SHEET 71 SUBTOTAL				-		-					14		70	14	70			-				-	-										
	SHEET 72 SUBTOTAL				-		-					84		42	84	42			-				-	-										
	SHEET 73 SUBTOTAL				-		-					28		70	28	70			-				-	-										
	SHEET 74 SUBTOTAL				-		-					28		84	28	84			-				-	-										
	SHEET 75 SUBTOTAL				-		-					14		56	14	56			-				-	-										
	SHEET 76 SUBTOTAL				-		-					-		42	-	42			-				-	-										
	SHEET 77 SUBTOTAL				-		-					14		28	14	28			-				-	-										
	SHEET SUBTOTAL				-		-					588		1414	588	1414			1				-	-										
	SHEET 78 SUBTOTAL				1016.92		30					-		(868)	-	-			1				8	1063.5										
	ROUNDING				- 59.08		- -					- 12		(7) 141	- 12	- 141							- -	36.5 -										
												FT 600	FT	FT 1555 (875)	FT 600	FT 1555	FT		EA 3	LB	LB	LB		LB 1100	LB	LB	LB							
TOTALS					SF 1075	SF	EA. 30	SF				FT 2155 (875)			FT 2155					LB			EA. 8	LB 1100				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

NON-OPTION ITEM

TRAFFIC SIGN SUMMARY SHEET #28

PROJECT NAME: NEW_HAVEN_-_FERRISBURGH
PROJECT NUMBER: NH_2503(I)S

FILE NAME: 05b038.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b038tss28.I
PLOT DATE: 31-JUL-2009 15:54
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 79 OF 87