COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

HES 010-1(38)				AC NH 2504(I)S						SUMMARY OF ESTIMATED QUANTITIES				DETAILED SUMMARY OF QUANTITIES			DETAILED SUMMARY OF QUANTITIES		
EROSION CONTROL	BRIDGE	FULL C.E.	ROADWAY	NON-PART.	EMPLOYEE TRAINEESHIP	EROSION CONTROL	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	QUANTITIES	UNIT	ITEMS	QUANTITIES	UNIT	ITEMS
-	-	-	5175	-	-	-	-	-	70	5245	CY	COMMON EXCAVATION	203.15	-						
-	-	-	-	-	-	-	-	-	525	525	CY	EARTH BORROW	203.30	EST.						
-	-	-	1350	-	-	-	-	-	-	1350	CY	SAND BORROW	203.31	EST.			REFER TO SHEETS 11, 12, 13, 82 AND 83 FOR DETAILED QUANTITY INFORMATION			
-	-	-	625	-	-	-	-	-	-	625	CY	TRENCH EXCAVATION OF EARTH	204.20	-						
-	-	-	1	-	-	-	-	-	1	2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.						
-	-	-	3250	-	-	-	-	-	44,150	47,400	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-						
-	-	-	-	-	-	-	-	-	500	500	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	-						
-	-	-	1925	-	-	-	-	-	-	1925	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	-						
-	-	-	-	-	-	-	-	-	620	620	TON	SUBBASE, RAP	301.40	EST.						
-	-	-	-	-	-	-	-	-	1100	1100	TON	AGGREGATE SHOULDERS, RAP	402.13	-						
-	-	-	25	-	-	-	-	-	300	325	CWT	EMULSIFIED ASPHALT	404.65	-						
-	-	-	0.2	-	-	-	-	-	0.8	1	TON	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-						
-	-	-	1875	-	-	-	-	-	13,850	15,725	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	490.30	-						
-	-	-	0.2	-	-	-	-	-	0.8	1	LU	AIR VOIDS PAY ADJUSTMENT	490.31	-						
-	-	-	0.2	-	-	-	-	-	0.8	1	LU	MAT DENSITY PAY ADJUSTMENT	490.32	-						
-	-	-	0.2	-	-	-	-	-	0.8	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT	490.33	-						
-	-	-	0.2	-	-	-	-	-	0.8	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT	490.34	-						
-	-	-	-	-	-	-	25	-	-	25	GAL	WATER REPELLENT, SILANE	514.10	EST.						
-	-	-	-	-	-	-	240	-	-	240	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	-						
-	-	-	-	-	-	-	300	-	-	300	LF	REMOVAL OF EXISTING RAILING	525.10	-						
-	-	-	-	-	-	-	138	-	-	138	LF	BRIDGE RAILING REPAIR, TYPE I	525.50	-						
-	-	-	-	-	-	-	163	-	-	163	LF	BRIDGE RAILING REPAIR, TYPE III	525.60	-						
-	-	-	-	-	-	-	100	-	-	100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.						
												BEGIN OPTION AA								
-	-	-	217	-	-	-	-	-	-	217	LF	18" CSP .064 (2-2/3 x 1/2)	601.0015	-						
-	-	-	217	-	-	-	-	-	-	217	LF	18" CPEP (SL)	601.2615	-						
												END OPTION AA								
												BEGIN OPTION BB								
-	-	-	4	-	-	-	-	-	-	4	EA	18" CSPES .064 (2-2/3 x 1/2)	601.6015	-						
-	-	-	4	-	-	-	-	-	-	4	EA	18" CPEPES	601.7015	-						
												END OPTION BB								
-	-	-	2	-	-	-	-	-	-	2	EA	CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.10	-						
-	-	-	-	-	-	-	-	-	1	1	EA	CHANGE ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-						
-	-	-	1	-	-	-	-	-	69	70	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-						
-	-	-	-	23	-	-	-	-	-	23	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-						
-	-	-	-	1	-	-	-	-	-	1	EA	CAST IRON COVER WITH FRAME	604.55	-						
-	-	-	-	1	-	-	-	-	-	1	EA	CAST IRON COVER WITH FRAME, SEWER	604.56	-						
-	-	-	500	-	-	-	-	-	-	500	LF	6 INCH UNDERDRAIN PIPE	605.10	-						
-	-	-	50	-	-	-	-	-	-	50	LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	-						
-	-	-	-	-	-	-	-	-	150	150	HR	POWER GRADER RENTAL	608.15	EST.						
-	-	-	25	-	-	-	-	-	100	125	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.						
-	-	-	100	-	-	-	-	-	60	160	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.						
-	-	-	-	-	-	-	-	-	250	250	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.						

PROJECT NAME: WILMINGTON
PROJECT NUMBER: AC_NH_2504(I)S_&_HES_010-1(38)

FILE NAME: p05b044.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM_FILE: p05b044g0.i
PLOT DATE: 23-AUG-2010
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 3 OF 125