COMPOSITE QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

HES 010-1(38)				AC NH 2504(I)S						SUMMARY OF ESTIMATED QUANTITIES				
EROSION CONTROL	BRIDGE	FULL C.E.	ROADWAY	NON-PART.	EMPLOYEE TRAINEESHIP	EROSION CONTROL	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
-	-	-	50	-	-	-	-	-	140	190	HR	TRUCK RENTAL	608.37	EST.
-	-	-	-	-	-	-	-	-	150	150	HR	LOADER RENTAL, TYPE I	608.40	EST.
-	-	-	90	-	-	-	-	-	720	810	CY	STONE FILL, TYPE I	613.10	-
-	-	-	10	-	-	-	-	-	-	10	CY	STONE FILL, TYPE II	613.11	-
-	-	-	-	-	-	-	-	-	190	190	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	-
-	-	-	-	-	-	-	-	-	4500	4500	LF	TREATED TIMBER CURB	616.35	-
-	-	-	12	-	-	-	-	-	14	26	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	-
-	-	-	-	-	-	-	-	-	1	1	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-
-	-	-	-	-	-	-	-	-	210	210	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	-
-	-	-	-	-	-	-	-	-	40	40	SY	DETECTABLE WARNING SURFACE	618.30	-
-	-	-	15	-	-	-	-	-	140	155	EA	YIELDING MARKER POSTS	619.17	EST.
-	-	-	-	-	-	-	-	-	13,200	13,200	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-
-	-	-	-	-	-	-	-	-	1250	1250	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/ 8 FEET POSTS	621.205	-
-	-	-	-	-	-	-	-	-	450	450	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	-
-	-	-	-	-	-	-	-	-	31	31	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
-	-	-	-	-	-	-	-	-	4	4	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	-
-	-	-	-	-	-	-	-	-	22	22	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
-	-	-	-	-	-	-	-	-	4	4	EA	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	-
-	-	-	-	-	-	-	-	-	1	1	EA	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE II	621.71	-
-	-	-	-	-	-	-	-	-	15,500	15,500	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
-	-	-	-	13	-	-	-	-	-	13	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
-	-	-	250	-	-	-	-	-	1000	1250	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
-	-	-	350	-	-	-	-	-	1500	1850	HR	FLAGGERS	630.15	EST.
-	-	0.2	-	-	-	-	-	0.8	-	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
-	-	0.2	-	-	-	-	-	0.8	-	1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
-	-	0.2	-	-	-	-	-	0.8	-	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
-	-	0.2	-	-	-	-	-	0.8	-	1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
-	-	-	-	-	520	-	-	-	-	520	HR	EMPLOYEE TRAINEESHIP	634.10	-
-	-	-	0.2	-	-	-	-	-	0.8	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
-	-	-	0.2	-	-	-	-	-	0.8	1	LS	TRAFFIC CONTROL	641.10	-
-	-	-	-	-	-	-	-	-	1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-
-	-	-	3	-	-	-	-	-	3	6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
-	-	-	3200	-	-	-	-	-	58,750	61,950	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	-
-	-	-	3200	-	-	-	-	-	54,250	57,450	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	-
-	-	-	-	-	-	-	-	-	400	400	LF	DURABLE 8 INCH WHITE LINE, THERMOPLASTIC	646.442	-
-	-	-	25	-	-	-	-	-	200	225	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	-
-	-	-	4	-	-	-	-	-	63	67	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
-	-	-	6400	-	-	-	-	-	83,500	89,900	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		REFER TO SHEETS 11, 12, 13, 82 AND 83 FOR DETAILED QUANTITY INFORMATION

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: WILMINGTON
PROJECT NUMBER: AC_NH_2504(I)S_&_HES_010-1(38)_

FILE NAME: p05b044.dgn__
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b044q02c.i
PLOT DATE: 23-AUG-2010
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 4 OF 125