STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
WILMINGTON: 103+54.0, LT	HAYSTACK RD						1				1			14 X		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0090 1322 0190	1	30	30	6.25																												BACK-TO-BACK SIGN ID CODE R1-1 2 REMOVALS		E-143
		1	6	10	0.42																												SIGN ID CODE VD-700		E-138
104+02.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			14 X		X		X															SIGN ID CODE VD-017		E-141
104+40.0, RT	SPEED LIMIT 35	1	30	36	7.50						1			14 X		X		X															SIGN ID CODE R2-1 1 REMOVAL	67	
105+40.0, RT	EAST	1	24	12	2.00						1			14 X		X		X															SIGN ID CODE M3-2		E-136B
	VERMONT 9	1	24	24	4.00																												SIGN ID CODE MI-5		E-136B
106+00.0, LT	DIST. 1 HWY GARAGE →	1	72	12	6.00						2			12 X 12		X		X															SIGN ID CODE D1-1 1 REMOVAL		E-123
108+82.0, LT	0090 1322 0200	1	6	10	0.42						1	8 X			X			X															SIGN ID CODE VD-700		E-138
110+22.0, RT							1				1			16 X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. 2 REMOVALS	-	-
	NEXT 1 MILE	1	24	18	3.00																												SIGN ID CODE W7-34 SIGN SHALL BE FLUORESCENT YELLOW GREEN		E-152
												LF ~~14~~ 8	LF	LF ~~98~~ 96	LF ~~14~~	LF ~~98~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 34.59	SF	EA. 2	SF							LF 112			LF ~~112~~					LB			EA.	LB				EA.	EA.	LB					

6 REMOVALS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC, AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: WILMINGTON
PROJECT NUMBER: AC NH 2504(1)S

FILE NAME: p05b044.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b044tss02.i
PLOT DATE: 23-AUG-2010
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 42 OF 125