STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAMES REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
WILMINGTON: 159+27.0, RT		1	30	30	6.25						1			13 X		X		X															SIGN ID CODE W11-2 2 REMOVALS SIGN SHALL BE FLUORESCENT YELLOW GREEN		E-152
							1																										SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
159+53.0, LT							1				1			16 X		X		X															4 REMOVALS SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
							1																										SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
160+08.5, RT	RESERVED PARKING	1	12	18	1.50						1			12 X		X		X															SIGN ID CODE R7-8	67	
160+86.0, RT		1	12	12	1.00						1			13 X		X		X															2 REMOVALS SIGN ID CODE R8-3A		E-143
	BEGIN	1	12	6	0.50																													67	
161+09.0, RT	STOP HERE ON RED	1	24	36	6.00						1			14 X		X		X															1 REMOVAL SIGN ID CODE R10-6		E-140
161+09 RT	BEGIN	1 1	12 12	12 6	1.00 0.5																												BEGIN REMOVED PER TOWN REQUEST 1 REMOVAL		
161+14.0, LT		1	12	12	1.00						1			14 X		X		X															SIGN ID CODE R8-3A 4 REMOVALS 1 REMOVAL PER TOWN		E-143
	END	1	12	6	0.50																												1 REMOVAL PER TOWN	67	
	RESERVED PARKING	1	12	18	1.50																												SIGN ID CODE R7-8	67	
161+32.0, LT	RAY HILL RD						1				1			14 X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0090 1322 0299	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK: 1 REMOVAL SIGN ID CODE R1-1 SIGN ID CODE VD-700 2 REMOVALS 19 REMOVALS		E-143 E-138
												LF	LF	LF ~~98~~ 96	LF	LF ~~98~~	LF		EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB					
TOTALS			SF ~~24.92~~ 26.42	SF	EA. 4	SF						LF ~~98~~ 96			LF ~~98~~						LB			EA.	LB										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC, AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #7

PROJECT NAME: WILMINGTON
PROJECT NUMBER: AC NH 2504(I)S

FILE NAME: p05b044.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b044tss07.i
PLOT DATE: 23-AUG-2010 14
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 47 OF 125