STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
WILMINGTON: 163+30.0, RT	EAST	1	24	12	2.00																											X	SIGN ID CODE M3-2 SIGN ASSEMBLY SHALL BE MOUNTED ON EXISTING SIGNAL POLE.		E-136B
	VERMONT 9	1	24	24	4.00																												SIGN ID CODE M1-5		E-136B
	NORTH SOUTH	1 1	24 24	12 12	2.00 2.00																												SIGN ID CODE M3-1 SIGN ID CODE M3-3		E-136B E-136B
	VERMONT 100 VERMONT 100	1 1	30 30	24 24	5.00 5.00																												SIGN ID CODE M1-5 SIGN ID CODE M1-5		E-136B E-136B
	← ↑	1 1	21 21	15 15	2.19 2.19																												SIGN ID CODE M6-1 SIGN ID CODE M6-3		E-136B E-136B
163+35.0, RT	R	1	12	12	1.00						1			13 X		X		X															SIGN ID CODE R8-3A 3 REMOVALS		E-143
	3 AM - 6 AM NOV 15 - APR 15	1	12	6	0.50																													67	
	BEGIN	1	12	6	0.50																												"BEGIN" PER TOWN 1 REMOVAL	67	
163+70 LT																																	1 REMOVAL		
164+38.0, LT	R	1	12	12	1.00						1			12 X		X		X															SIGN ID CODE R8-3A 6 REMOVALS		E-143
	3 AM - 6 AM NOV 15 - APR 15	1	12	6	0.50																													67	
	BEGIN	1	12	6	0.50																												"BEGIN" REMOVED PER TOWN 1 REMOVAL	67	
											LF	LF	LF ~~28~~ 25	LF	LF ~~28~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
TOTALS			SF 28.38	SF	EA.	SF						LF ~~28~~ 25			LF ~~28~~				LB			EA.	LB				EA.	EA.	LB					

20 REMOVALS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC, AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #9

PROJECT NAME: WILMINGTON
PROJECT NUMBER: AC NH 2504(1)S

FILE NAME: p05b044.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b044tss09.i
PLOT DATE: 23-AUG-2010 14
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 49 OF 125