STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																						
WILMINGTON: 164+80.0, RT	R8-3A	1	12	12	1.00						1			13 X		X		X															SIGN ID CODE R8-3A		E-143
	3 AM - 6 AM NOV 15 - APR 15	1	12	6	0.50																											2 REMOVALS	67	
	END	1	12	6	0.50																											REMOVED PER TOWN 1 REMOVAL	67	
165+42.0, RT	CHURCH ST						1				1			12 X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	4 REM. -	-
	STOP 0090 1322 0305	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE R1-1 "STOP" REMOVED PER TOWN SIGN ID CODE VD-700 1 REMOVAL		E-143 E-138
165+42 RT	ONE-WAY ONE-WAY	1 1	36 36	12 12	3.0 3.0																											ONE-WAYS ADDED BACK TO BACK		
165+45.0, RT	R8-3A	1	12	12	1.00						1			12 X		X		X															SIGN ID CODE R8-3A		E-143
164+54 LT																																	2 REMOVALS		
165+93.0, LT	R8-3A	1	12	12	1.00						1			12 X		X		X															SIGN ID CODE R8-3A 2 REMOVALS		E-143
166+50.0, RT	SPEED LIMIT 25	1	24	30	5.00						1			14 X		X		X															SIGN ID CODE R2-1		E-142
166+84																																	2 REMOVALS		
169+15.0, RT	R8-3A	1	12	12	1.00						1			12 X		X		X															SIGN ID CODE R8-3A 1 REMOVAL		E-143
167+32 LT	SEARSBURG 7 BENNINGTON 21 SKI AREAS → EAST JAMAICA 24						4				2			15 15																			4 REMOVALS		
169+53.0, RT	BEAVER ST						1				1			14 X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	2 REM.	-
	STOP 0090 1322 0313	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK: SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
												LF	LF	LF ~~98~~ 119	LF	LF ~~98~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB						21 REMOVALS		
TOTALS		SF ~~23.34~~ 29.34	SF	EA. ~~2~~ 6	SF							LF ~~98~~ 119			LF ~~98~~					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC, AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #10

PROJECT NAME: WILMINGTON
PROJECT NUMBER: AC NH 2504(I)S

FILE NAME: p05b044.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b044tss10.i
PLOT DATE: 23-AUG-2010
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 50 OF 125