STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															OPTION ITEMS																						
WILMINGTON: 196+35.0, LT	BRIDGE 33 VT 9	1	6	8	0.33						~~1~~	~~X~~			X			X																ATTACHED TO EXISTING SIGN ID CODE VD-701		E-134
196+45.0, RT	BRIDGE 33 VT 9	1	6	8	0.33						1	8 X			X			X																SIGN ID CODE VD-701		E-134
199+30.0, LT	WHITES RD						1				1			14 X		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	4 REM. -	-
	STOP 0090 1322 0370	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
204+76.0, RT	0090 1322 0380	1	6	10	0.42						1	8 X			X			X																SIGN ID CODE VD-700		E-138
206+67.0, RT		1	30	30	6.25						1			14 X		X		X																SIGN ID CODE W1-2R 1 REMOVAL		E-151
208+50.0, RT	HIDDEN DRIVES	1	30	30	6.25						1			14 X		X		X																SIGN ID CODE VW-060 1 REMOVAL		E-154
212+44.0, RT	SPEED LIMIT 40	1	24	30	5.00						~~1~~			~~X~~		X		X																SIGN ID CODE R2-1 1 REMOVAL		E-142
213+32.0, LT	HIDDEN DRIVES	1	30	30	6.25						1			14 X		X		X																SIGN ID CODE VW-060 1 REMOVAL		E-154
												LF ~~42~~ 16	LF	LF ~~70~~ 56	LF ~~42~~	LF ~~70~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
	TOTALS		SF 31.50	SF	EA. 1	SF						LF ~~112~~ 72			LF ~~112~~						LB			EA.		LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC, AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #13

8 REMOVALS

PROJECT NAME: WILMINGTON
PROJECT NUMBER: AC NH 2504(I)S

FILE NAME: p05b044.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b044+ssl3.i

PLOT DATE: 23-AUG-2010 14
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 53 OF 125