STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 21

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAMES REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
WILMINGTON: 328+81.0, LT		1	30	30	6.25						1			16 X		X		X															IREMOVAL	68	
		1	24	18	3.00																												SIGN ID CODE W7-3a		E-152
322+73 RT																																	IREMOVAL		
330+23.0, LT							1				1			14 X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
		1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700 3 REMOVALS		E-143 E-138
330+65.0, LT		1	24	30	5.00						1			14 X		X		X															SIGN ID CODE VR-017		E-141
331+53.0, RT		1	6	10	0.42						1	8 X			X			X															SIGN ID CODE VD-700		E-138
332+56.0, RT		1	6	8	0.33						1	8 X			X			X															SIGN ID CODE VD-701		E-134
333+44.0, RT		1	24	30	5.00						1			14 X		X		X															SIGN ID CODE R4-3 IREMOVAL		E-141
333+50.0, LT		1	6	8	0.33						1	8 X			X			X															SIGN ID CODE VD-701		E-134
334+38 RT																																	IREMOVAL		
												LF 42 24	LF	LF 56 58	LF 42	LF 56	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
																																	7 REMOVALS		
TOTALS		SF 27.00	SF	EA. 1	SF							LF 98 82			LF 98					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC, AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #21

PROJECT NAME: WILMINGTON
PROJECT NUMBER: AC NH 2504(I)S

FILE NAME: p05b044.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b044tss21.i

PLOT DATE: 23-AUG-2010 14
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 61 OF 125