STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 24

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																									
WILMINGTON: 362+00.0, RT		1	36	36	9.00						2			14 X 16																			SIGN ID W4-2	I REMOVAL SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS.		E-151
363+26.0, LT		1	6	10	0.42						1	8 X			X			X															SIGN ID VD-700	I REMOVAL		E-138
367+52.0, LT		1	30	30	6.25						1			16 X		X		X															SIGN ID CODE W7-1b	I REMOVAL	68	
		1	24	18	3.00																											SIGN ID CODE W7-3A			E-152
371+00.0, RT		1	30	30	6.25						1			16 X		X		X															SIGN ID CODE W11-1 SIGN SHALL BE FLUORESCENT YELLOW GREEN			E-153B
		1	24	30	5.00																											SIGN ID CODE W16-1 SIGN SHALL BE FLUORESCENT YELLOW GREEN			E-153B
371+00.0, LT		1	30	30	6.25						1			16 X		X		X															SIGN ID CODE W11-1 SIGN SHALL BE FLUORESCENT YELLOW GREEN			E-153B
		1	24	30	5.00																											SIGN ID CODE W16-1 SIGN SHALL BE FLUORESCENT YELLOW GREEN			E-153B
372+63 RT																																I REMOVAL			
373+95.0, RT		1	6	8	0.33						~~1~~	~~X~~			X			X															SIGN ID CODE VD-701			E-134
		1	6	10	0.42						1	8 X			X			X															SIGN ID CODE VD-700			E-138
374+10.0, LT		1	6	8	0.33						1	8 X			X			X															SIGN ID CODE VD-701			E-134
375+49.0, RT		1	36	36	9.00						2			14 X 16																			2 REMOVAL SIGN ID CODE VW-619	SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS.		E-151
												LF ~~56~~ 24	LF	LF ~~42~~ (56) 108	LF ~~56~~	LF ~~42~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB						6 REMOVALS		
TOTALS			SF 51.25	SF	EA.	SF						LF ~~98~~ (56) 132			LF ~~98~~						LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC, AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #24

PROJECT NAME: WILMINGTON
PROJECT NUMBER: AC NH 2504(I)S

FILE NAME: p05b044.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b044tss24.i
PLOT DATE: 23-AUG-2010
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 64 OF 125