



HIGHWAY NAME	RWA	ERW	RW500	RWN	OTHER
VT. ROUTE 9 - BEGIN PROJECT	2	1	2	1	1-PORTABLE CHANGEABLE MESSAGE SIGN
HAYSTACK ROAD (TH-9)	1	1			
RAY HILL (TH-8)	1	1			
SOUTH MAIN STREET (TH-33)	1	1			
VT. ROUTE 100 NORTH	2	1	2		1-PORTABLE CHANGEABLE MESSAGE SIGN
CHURCH STREET (TH-63)	1	1			
BEAVER STREET (TH-64)	1	1			
COUNTRY CLUB ROAD (TH-72)	1	1			
WHITES ROAD (TH-23)	1	1			
VT. ROUTE 100 SOUTH	2	1	2		
BALLOU HILL ROAD (TH-26)	1	1			
SHEARER HILL ROAD (TH-40)	1	1			
CHARLES FOREST ROAD (TH-88)	1	1			
LAKE RAPUNDA (TH-4)	1	1			
LARSON ROAD (TH-28)	1	1			
SPARROW LANE (TH-95)	1	1			
STATE FOREST HIGHWAY	1	1			
HALL ROAD (TH-27)	1	1			
VT. ROUTE 9 - END PROJECT	2	1	2	1	1-PORTABLE CHANGEABLE MESSAGE SIGN
TOTAL	23	19	8	2	3-PORTABLE CHANGEABLE MESSAGE SIGN

CONSTRUCTION APPROACH SIGNING

- NOTES:
- SEE VAOT STD. E-100 FOR ADDITIONAL SIGN PLACEMENT.
 - CONSTRUCTION ZONE SIGN LAYOUT SHALL BE IN ACCORDANCE WITH SECTION 6 OF THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
 - CONSTRUCTION SIGNS SHALL BE IN NEW OR LIKE NEW CONDITION PER VAOT STANDARDS.
 - DIAMOND SHAPED SIGNS SHALL BE 4' X 4' WITH BLACK LEGEND ON FLUORESCENT ORANGE BACKGROUND.
 - RETROREFLECTIVE SHEETING SHALL BE TYPE VII OR BETTER.
 - CONSTRUCTION ZONE SIGNS SHALL BE INSTALLED ON-TWO-POSTS-EACH-OR-AS-AN NCHRP 350 COMPLIANT SIGN/STAND SYSTEM.
 - PORTABLE CHANGEABLE MESSAGE SIGNS ARE OPTIONAL AND ARE TO BE USED AS DIRECTED BY THE RESIDENT ENGINEER.
 - PAYMENT FOR CONSTRUCTION SIGNING WILL BE MADE UNDER ITEM 641.10 TRAFFIC CONTROL.
 - THE CONTRACTOR SHALL COORDINATE ALL CONSTRUCTION SIGNING WITH THE HES 010-I(38) PROJECT SO THERE ARE NO CONFLICTS AS DIRECTED BY THE RESIDENT ENGINEER. SEE SHEET 117 FOR HES 010-I(38) CONSTRUCTION APPROACH SIGNING SHEET.

NOT TO SCALE CONSTRUCTION APPROACH SIGNING DETAIL SHEET	PROJECT NAME: WILMINGTON	PLOT DATE: 23-AUG-2010
	PROJECT NUMBER: AC_NH_2504(I)S	DRAWN BY: C.A.K.
	FILE NAME: p05b044.dgn	DESIGNED BY: M.J.M.
	IPARM FILE: p05b044cas.i	CHECKED BY: D.W.E.
		SHEET 78 OF 125