QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
-	-	-	5175	5175	CY	COMMON EXCAVATION	203.15	EST.
-	-	-	1350	1350	CY	SAND BORROW	203.31	EST.
-	-	-	625	625	CY	TRENCH EXCAVATION OF EARTH	204.20	4
-	-	-	1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
-	-	-	3250	3250	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	60
-	-	-	1925	1925	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	EST.
-	-	-	25	25	CWT	EMULSIFIED ASPHALT	404.65	2
-	-	-	0.2	0.2	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
-	-	-	1875	1875	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	490.30	7
-	-	-	0.2	0.2	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
-	-	-	0.2	0.2	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
-	-	-	0.2	0.2	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
-	-	-	0.2	0.2	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
						BEGIN OPTION AA		
-	-	-	217	217	LF	18" CSP .064 (2-2/3 x 1/2)	601.0015	-
-	-	-	217	217	LF	18" CPEP (SL)	601.2615	-
-	-	-	217	217	LF	18" CPEP (SL) END OPTION AA	601.2615	-
-	-	-	4	4	EA	18" CSPES .064 (2-2/3 x BEGIN OPTION BB	601.6015	-
-	-	-	4	4	EA	18" CSPES .064 (2-2/3 x 1/2)	601.6015	-
-	-	-	4	4	EA	18" CPEPES	601.7015	-
						END OPTION BB		
-	-	-	2	2	EA	CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.10	-
-	-	-	1	1	EA	REHAB. DROP INLETS, CATCH BASINS OR MANHOLES, CLASS I	604.412	-
-	-	-	500	500	LF	6 INCH UNDERDRAIN PIPE	605.10	EST.
-	-	-	50	50	LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	EST.
-	-	-	25	25	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
-	-	-	100	100	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
-	-	-	50	50	HR	TRUCK RENTAL	608.37	EST.
-	-	-	90	90	CY	STONE FILL, TYPE I	613.10	EST.
-	-	-	10	10	CY	STONE FILL, TYPE II	613.11	EST.
-	-	-	12	12	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	0.5
-	-	-	15	15	EA	YIELDING MARKER POSTS	619.17	EST.
-	-	-	250	250	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
-	-	-	350	350	HR	FLAGGERS	630.15	EST.
-	-	0.2	-	0.2	LS	FIELD OFFICE, ENGINEERS	631.10	-
-	-	0.2	-	0.2	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
-	-	0.2	-	0.2	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
-	-	0.2	-	0.2	LU	FIELD OFFICE TELEPHONE	631.25	-
-	-	-	0.2	0.2	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
-	-	-	0.2	0.2	LS	TRAFFIC CONTROL	641.10	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
3000	SY	MAINLINE
190	SY	DRIVEWAYS
60	SY	ROUNDING
3250	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-28)
		VT. ROUTE 9
253	TON	WEARING COURSE (TYPE IVS)
84	TON	LEVELING COURSE (TYPE IVS)
26	TON	DRIVES
41	TON	PULLOUTS
		VT. ROUTE 100
236	TON	WEARING COURSE (TYPE IVS)
614	TON	BINDER COURSE (TYPE IIS)
614	TON	BASE COURSE (TYPE IIS)
7	TON	ROUNDING
1875	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: WILMINGTON
PROJECT NUMBER: HES_010-1(38)

FILE NAME: p05c324.dgn
PROJECT LEADER: DEG
DESIGNED BY: DWE
QUANTITY SHEET QU-1

PLOT DATE: [illegible]
DRAWN BY: CAK
CHECKED BY: DWE
SHEET 82 OF 125