STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												NON-OPTION ITEMS ( )																									
VT. ROUTE 9 224+00.0, RT	EAST	1	24	12	2.00						1			14 X		X		X															SIGN ID CODE M3-2		E-136B
	VERMONT 9	1	24	24	4.00																												SIGN ID CODE MI-5		E-136B
VT. ROUTE 100 120+00.0, RT		1	30	30	6.25						1			14 X		X		X															SIGN ID CODE WII-2 SIGN SHALL BE FLUORESCENT YELLOW GREEN		E-152
122+00.0, RT		1	36	36	9.00						2			14 X 14																			SIGN ID CODE W3-1A SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS.		E-150
124+00.0, LT	JACKSONVILLE 6 WHITINGHAM 9	1 1	72 72	12 12	6.00 6.00						2			14 X 14																			SIGN ID CODE DI-1 SIGN ID CODE DI-1 SIGNS SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS.		E-123 E-123
117+70 RT																																	2 REMOVALS		
124+00.0, RT	JCT	1	21	15	2.19						1			14 X		X		X															SIGN ID CODE M2-1		E-136B
	VERMONT 9	1	24	24	4.00																												SIGN ID CODE MI-5		E-136B
120+00.0, RT		1	30	30	6.25						1			14 X		X		X															SIGN ID CODE WII-1 SIGN SHALL BE FLUORESCENT YELLOW GREEN		E-153B
	SHARE THE ROAD	1	24	30	5.00																												SIGN ID CODE W16-1 SIGN SHALL BE FLUORESCENT YELLOW GREEN		E-153B
126+00.0, LT	SPEED LIMIT 50	1	24	30	5.00						1			14 X		X		X															SIGN ID CODE R2-1		E-142
126+25.0, RT	WILMINGTON 1 BENNINGTON 22	1 1	72 72	12 12	6.00 6.00						2												10 2 10	152 ~~191.7~~									SIGN ID CODE DI-1 SIGN ID CODE DI-1		E-123 E-123
	MARLBORO 8 BRATTLEBORO 18	1 1	72 72	12 12	6.00 6.00																												SIGN ID CODE DI-1 SIGN ID CODE DI-1 9 REMOVALS		E-123 E-123
123+75																																	4 REMOVALS		
128+00.0, LT	SOUTH	1	24	12	2.00						1			14 X		X		X															SIGN ID CODE M3-3		E-136B
	VERMONT 100	1	30	24	5.00																												SIGN ID CODE MI-5		E-136B
												LF	LF	LF ~~84.0~~ ~~(56.0)~~ 140	LF	LF ~~84.0~~	LF		EA	LB	LB	LB		LB ~~191.7~~ 152	LB	LB	LB						15 REMOVALS		
TOTALS			SF 86.69	SF	EA.	SF						LF ~~84.0~~ ~~(56.0)~~ 140			LF ~~84.0~~					LB			EA. 2	LB 152 ~~191.7~~				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC & SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: WILMINGTON
PROJECT NUMBER: HES_010-I(38)
FILE NAME: 05c324.dgn
PROJECT LEADER: DEG
DESIGNED BY: DWE
TRAFFIC_SIGN_SUMMARY_SHEET_I
PLOT DATE: ~~23-AUG-2005~~
DRAWN BY: CAK
CHECKED BY: DWE
SHEET 115 OF 125