STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL 2.0	FLANGED CHANNEL 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL 2.0 lb/ft 2.16	SQUARE STEEL 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM 4.0 lb/ft 1.7	TUBULAR ALUMINUM 4.0 MOD lb/ft 1.7	FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL 3.5 lb/ft 9.0	TUBULAR STEEL 4.0 lb/ft 10.8	TUBULAR STEEL 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												NON-OPTION ITEMS ( )																							
VT. ROUTE 100 128+00.0, RT	WEST NORTH EAST	1 1 1	24 24 24	12 12 12	2.00 2.00 2.00						2												11 2 11	167.2 ~~197.4~~								X	SIGN ID CODE M3-1 SIGN ID CODE M3-4 SIGN ID CODE M3-2		E-136B E-136B E-136B
	VERMONT 9 / VERMONT 100 / VERMONT 9	1 1 1	30 24 30	24 24 24	5.00 4.00 4.00																												SIGN ID CODE M1-5 SIGN ID CODE M1-5 SIGN ID CODE M1-5		E-136B E-136B E-136B
	← ← →	1 1 1	21 21 21	15 15 15	2.19 2.19 2.19																												SIGN ID CODE M6-1 SIGN ID CODE M6-1 SIGN ID CODE M6-1		E-136B E-136B E-136B
129+06 129+10																																	1 REMOVAL 1 REMOVAL		
130+35.0, LT	STOP	1	30	30	6.25		1				1			14 X		X		X															SIGN ID CODE R1-1 1 REMOVAL		E-143
129+72																																	1 REMOVAL		
130+35.0, RT	STOP	1	30	30	6.25						1			14 X		X		X															SIGN ID CODE R1-1 2 REMOVALS		E-143
	0090 1322 0419	1	6	8	0.33																												SIGN ID CODE VD-700		E-138
130+21 RT																																	1 REMOVAL 7 REMOVALS		
												NON-OPTION ITEMS																			REM.				
	TOTAL THIS SHEET TOTAL SHEET 114 TOTAL SHEET 115				38.40 85.95 86.69		~~1~~ 1 -							(-) (-) ~~(56)~~		(-) (-) (-)							2 8 2	~~197.4~~ ~~744.2~~ ~~191.7~~	167.2 699.2 152.0						7 29 15				
												OPTION ITEMS																							
	TOTAL THIS SHEET TOTAL SHEET 114 TOTAL SHEET 115				- - -		- - -						140	28.0 14.0 ~~84.0~~		~~28.0~~ ~~14.0~~ ~~84.0~~																			
	ROUNDING				~~0.96~~		-							~~24.0~~ ~~(19.0)~~		~~24.0~~ ~~(-)~~								~~16.7~~											
												LF	LF	LF ~~150.0~~ ~~(75.0)~~	LF	LF ~~150.0~~ ~~(-)~~	LF		EA	LB	LB	LB		LB 1150	LB	LB	LB						51 REMOVALS		
	TOTALS				SF ~~212~~ 211.04	SF	EA. ~~1~~ 2	SF				LF ~~150.0~~ ~~(75.0)~~ 182			LF ~~150.0~~ ~~(-)~~					LB			EA. 12	LB ~~1150~~ 1018.4				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC & SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #3

PROJECT NAME: WILMINGTON
PROJECT NUMBER: HES 010-1(38)
FILE NAME: 05c324.dgn
PLOT DATE: [illegible]
PROJECT LEADER: DEG
DRAWN BY: CAK
DESIGNED BY: DWE
CHECKED BY: DWE
TRAFFIC_SIGN_SUMMARY_SHEET_TSS33_
SHEET 116 OF 125