

QUANTITY SHEET 4

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
		FULL C.E. ITEMS	BRIDGE	TRAINING	ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					530	530		LB	SEED	651.15	10.0	SEED		
					3500	3500		LB	FERTILIZER	651.18	EST.	270	LB	DITCH CLEANING
					14	14		TON	AGRICULTURAL LIMESTONE	651.20	EST.	250	LB	SIDE SLOPE TREATMENTS
					14	14		TON	HAY MULCH	651.25	EST.	10	LB	ROUNDING
					500	500		CY	TOPSOIL	651.35	EST.	530	LB	TOTAL
					10,000	10,000		SY	GRUBBING MATERIAL	651.40	27.8	TEMPORARY EROSION MATTING		
					28,000	28,000		SY	TEMPORARY EROSION MATTING	653.20	139.8	16,188	SY	DITCH CLEANING
					25,000	25,000		LF	EROSION LOG	653.60	EST.	11,672.2	SY	SIDE SLOPE TREATMENTS
					239	239		SF	TRAFFIC SIGNS, TYPE A	675.20	0.4	139.8	SY	ROUNDING
					1700	1700		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	48.0	28,000	SY	TOTAL
					135	135		EACH	REMOVING SIGNS	675.50		SQUARE TUBE SIGN POST AND ANCHOR		
					58	58		EACH	ERECTING SALVAGED SIGNS	675.60		1106	LF	TRAFFIC SIGN SUMMARY SHEET
					81	81		EACH	DELINEATOR WITH STEEL POST	676.10		546	LF	ESTIMATED QUANTITY
					16	16		EACH	REMOVAL OF EXISTING DELINEATOR	676.12		48	LF	ROUNDING
					1	1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50		1700	LF	TOTAL
					16	16		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM)	900.620		REMOVING SIGNS		
					19,250	19,250		LF	SPECIAL PROVISION (BOX BEAM GUARDRAIL W/7 FEET POSTS)	900.640	158.0	98	EACH	TRAFFIC SIGN SUMMARY SHEET
			1000		1000	1000		LF	SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED 2 RAIL BOX BEAM/FASCIA MOUNTED)	900.640	18.75	37	EACH	ESTIMATED QUANTITY
					152,000	152,000		SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	1391.0	135	EACH	TOTAL
					2200	2200		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	98.0	ERECTING SALVAGED SIGNS		
					152,000	152,000		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	1391.0	21	EACH	TRAFFIC SIGN SUMMARY SHEET
					49,650	49,650		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	39.0	37	EACH	ESTIMATED QUANTITY
					2825	2825		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	14.0	58	EACH	TOTAL
					225	225		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	5.0	SPECIAL PROVISION (COLD MIXED RECYCLED BIT. PAVEMENT, PORTLAND CEMENT)		
					1200	1200		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-IH OR CRS-IH)	900.683	21.0	142,904	SY	MAINLINE
					1900	1900		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	16.0	6933	SY	SIDE ROADS

QUANTITY SHEET #4

PROJECT NAME: WARREN - WAITSFIELD
 PROJECT NUMBER: STP 2506(1)
 FILE NAME: p05b048.dgn
 PROJECT LEADER: D.E.G.
 DESIGNED BY: M.J.M.
 IPARM FILE: p05b048quan4.i
 PLOT DATE: 12/21/2012
 DRAWN BY: W.G.P.
 CHECKED BY: D.E.G.
 SHEET 12 OF 310

FILE NAME: U:\1762\CADD\MSTN\STP_2506\p05b048_Contract_Plan.dgn
DATE/TIME: 12/21/2012
USER: 4866