STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGNS	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
WARREN: 147+84.0, RT	1000 1217 0280	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700			E-138
158+40.0, LT	1000 1217 0300	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700			E-138
168+96.0, RT	1000 1217 0320	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700			E-138
175+11.0, RT	Main St STOP 1000 1217 0331	1	36	12	3.00																												DOUBLE SIDED SIGN, SIGN ID CODE D3-1. 12" TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		113	
		1	6	10	0.42		1				1					X		X															BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700	-	-	- E-138
176+58.0, LT	Bobbin Mill Rd Bobbin Mill Rd	1 1	60 60	12 12	5.00 5.00						2					X		X															BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1		113 113	
176+66.0, LT	STOP 1000 1217 0336	1	6	10	0.42		1				1					X		X															BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700	-	-	- E-138
181+22.0, LT	Lincoln Gap Rd Lincoln Gap Rd	1 1	60 60	12 12	5.00 5.00						2					X		X															BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1		113 113	
181+32.0, LT	STOP 1000 1217 0345	1	6	10	0.42		1				2					X		X															BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POSTS. SIGN ID CODE VD-700	-	-	- E-138
												LF	LF	LF	LF 42	LF 112	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF 25.52	SF	EA. 3	SF				LF			LF 154					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #3

PROJECT NAME: WARREN - WAITSFIELD
PROJECT NUMBER: STP 2506(1)

FILE NAME: p05b048.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b048tss3.1

PLOT DATE: 12/20/2012
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 105 OF 310

FILE NAME = U:\17762\CADD\MSTN\STP 2506\p05b048_Contract Plans.dgn
DATE/TIME = 12/20/2012
USER = 4886