STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGNING	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
WARREN: 283+18.0, LT	STOP 1000 1217 0537	1	6	10	0.42		1				1					X		X															BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700	-	-	- E-138
294+44.0, LT	Powderhound Rd Powderhound Rd	1 1	72 72	12 12	6.00 6.00						2					X		X															BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1		114 114	
294+50.0, LT	STOP 1000 1217 0559	1	6	10	0.42		1				1					X		X															BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POSTS. SIGN ID CODE VD-700	-	-	- E-138
294+56.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS						1				1					X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-	-
296+62.0, LT	Sugarbush Access Rd Sugarbush Access Rd	1 1	72 72	12 12	6.00 6.00						2					X		X															BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1		114 114	
296+79.0, LT	STOP 1000 1217 0562	1 1	30 6	30 10	6.25 0.42						1					X		X															BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		 E-138
304+13.0, RT	XX MPH	1	18	18	2.25				1																									NEW SIGN TO BE MOUNTED ON EXISTING POST. SIGN ID CODE W13-1P	X		
306+24.0, RT	1000 1217 0580	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700			E-138
												LF	LF	LF	LF 14	LF 112	LF	EA.	LB	LB	LB		LB	LB	LB	LB									
TOTALS		SF 34.18	SF	EA. 3	SF							LF			LF 126				LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #6

PROJECT NAME: WARREN - WAITSFIELD
PROJECT NUMBER: STP 2506(1)

FILE NAME: p05b048.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b048tss6.i

PLOT DATE: 12/20/2012
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 108 OF 310

FILE NAME = U:\1762\CADD\MSTN\STP 2506\p05b048_Contract Plans.dgn
DATE/TIME = 12/20/2012
USER = 4885