STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
WARREN: M 3+10.0, RT	SPEED LIMIT 25	1	24	30	5.00						1					X		X															SIGN ID CODE R2-1	X		
WAITSFIELD: 10+56.0, LT	1000 1216 0020	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700			E-138
17+43.0, LT	Butternut Hill Rd	1	66	12	5.50						2					X		X															BACK-TO-BACK		114	
	Butternut Hill Rd	1	66	12	5.50																											SIGN ID CODE D3-1		114	
																																SIGN ID CODE D3-1			
17+50.0, LT	STOP 1000 1216 0034	1	6	10	0.42		1				1					X		X															BACK TO BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700			E-138
21+48.0, RT	Bundy Rd STOP 1000 1216 0040	1	42	12	3.50																											DOUBLE SIDED SIGN, SIGN ID CODE D3-1. 12" TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		114	
		1	6	10	0.42		1				1					X		X													BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700	-	-	- E-138
31+68.0, LT	1000 1216 0060	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700			E-138
35+06.0, RT	Rolston Rd STOP 1000 1216 0066	1	42	12	3.50																											DOUBLE SIDED SIGN, SIGN ID CODE D3-1. 12" TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		114	
		1	6	10	0.42		1				1					X		X													BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700	-	-	- E-138
42+24.0, LT	1000 1216 0080	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700			E-138
												LF	LF	LF	LF 42	LF 84	LF	EA.		LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 25.52	SF	EA. 3	SF							LF			LF 126					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #8

PROJECT NAME: WARREN - WAITSFIELD
PROJECT NUMBER: STP 2506(1)

FILE NAME: p05b048.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b048tss8.1

PLOT DATE: 12/20/2012
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 110 OF 310

FILE NAME = U:\17752\CADD\MSTN\STP 2506\p05b048_Contract Plans.dgn
DATE/TIME = 12/20/2012
USER = MDS