STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGNS	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
WAITSFIELD: 52+62.0, LT	Kingsbury Rd Kingsbury Rd	1 1	54 54	12 12	4.50 4.50						2					X		X																BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1		114 114	
52+75.0, LT	STOP 1000 1216 0100	1	6	10	0.42		1				1					X		X																BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700	-	-	- E-138
63+36.0, RT	1000 1216 0120	1	6	10	0.42						1				X			X																SIGN ID CODE VD-700			E-138
73+60.0, LT	1000 1216 0140	1	6	10	0.42						1				X			X																SIGN ID CODE VD-700			E-138
84+48.0, LT	1000 1216 0160	1	6	10	0.42						1				X			X																SIGN ID CODE VD-700			E-138
95+04.0, RT	1000 1216 0180	1	6	10	0.42						1				X			X																SIGN ID CODE VD-700			E-138
101+02.0, LT		1	12	36	3.00						1					X		X																SIGN ID CODE OM-3L	X		
104+80.0, LT	Lareau Rd STOP 1000 1216 0199	1	42	12	3.50																												DOUBLE SIDED SIGN, SIGN ID CODE D3-1. 12" TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		114	
		1	6	10	0.42		1				1					X		X															BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST. SIGN ID CODE VD-700	-	-	- E-138
												LF	LF	LF	LF 56	LF 70	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 18.02	SF	EA. 2	SF				LF			LF 126					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #9

PROJECT NAME: WARREN - WAITSFIELD
PROJECT NUMBER: STP 2506(1)

FILE NAME: p05b048.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p05b048tss9.1

PLOT DATE: 12/20/2012
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 111 OF 310

FILE NAME = U:\17752\CADD\MSTN\STP 2506\p05b048_Contract Plans.dgn
DATE/TIME = 12/20/2012
USER = 4885