QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						25	25	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
						9	9	EA	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	-
						11	11	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
						8500	8500	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	355
						700	700	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
						5000	5000	HR	FLAGGERS	630.15	EST
			1				1	LS	FIELD OFFICE, ENGINEERS	631.10	-
			1				1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
			1				1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			1				1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
						1	1	LS	MOBILIZATION / DEMOBILIZATION	635.11	-
						1	1	LS	TRAFFIC CONTROL	641.10	-
						1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-
						4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						75000	75000	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	1367
						75000	75000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	1759
						390	390	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	20
						133	133	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
						25	25	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	3
						144000	144000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	3206
						143000	143000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	3145
						390	390	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	20
						133	133	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
						25	25	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	3
						2900	2900	EA	LINE STRIPING TARGETS	646.76	133
						3350	3350	SY	GEOTEXTILE UNDER STONE FILL	649.31	120
						75	75	LB	SEED	651.15	7
						590	590	LB	FERTILIZER	651.18	25
						2.50	2.50	TON	AGRICULTURAL LIMESTONE	651.20	0.24
						2.50	2.50	TON	HAY MULCH	651.25	0.24
						630	630	CY	TOPSOIL	651.35	22
						4500	4500	SY	TEMPORARY EROSION MATTING	653.20	136
						265	265	SF	TRAFFIC SIGN, TYPE A	675.20	16.20
						680	680	LF	SQUARE TUBE SIGN POSTS AND ANCHORS	675.341	20

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: MORETOWN-DUXBURY-MORETOWN
PROJECT NUMBER: STP 2507 (1)S

FILE NAME: p05b050.DGN
PROJECT LEADER: EPD
DESIGNED BY: CDL
PLOT FILE: p05b050qs2.i

PLOT DATE: 31-OCT-2012 16:08
DRAWN BY: RHB
CHECKED BY: EPD
SHEET 7 OF 33