STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
STA. 45+46 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X																	VR-017		E-141
STA. 102+58 LT	STOP TURNER HILL RD	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN.		E-143
	1000 1206 0196	1	6	10	0.42						1					X																MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-138
STA. 103+14 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X																VR-017		E-141
STA. 135+14 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X																VR-017		E-141
STA. 135+56 RT	STOP WILDER RD	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN.		E-143
	1000 1206 0257	1	6	10	0.42						1					X																MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-138
STA. 143+45 LT	STOP RYAN RD	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN.		E-143
	1000 1206 0273	1	6	10	0.42						1					X																MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-138
STA. 143+87 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X																VR-017		E-141
STA. 170+70 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X																VR-017		E-141
STA. 171+26 RT	STOP STEVENS BROOK RD	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN.		E-143
	1000 1206 0325	1	6	10	0.42						1					X																MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-138
												FT	FT	FT	FT	FT 135	FT		EA	LB	LB	LB		LB	LB	LB	LB								
					SF 51.68	SF	EA. 4	SF				FT			FT 135					LB	EA.	LB					EA.	EA.	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 2

PROJECT NAME: MORETOWN-DUXBURY-MORETOWN
PROJECT NUMBER: STP 2507 (I)S

FILE NAME: p05b050.DGN
PROJECT LEADER: EPD
DESIGNED BY: CDL
PLOT FILE: p05b050tss2.i

PLOT DATE: 31-OCT-2012 16:09
DRAWN BY: RHB
CHECKED BY: EPD
SHEET 30 OF 33