STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA. 298+30 LT	STOP MAIN ST	1	30	30	6.25		1				1					X																	RI-1 MOUNT STREET SIGN OVER STOP SIGN.		E-143
	1000 1206 0565	1	6	10	0.42																												MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-138
STA. 298+75 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X																	VR-017		E-141
STA. 298+80 RT	STOP	1	30	30	6.25						1					X																	RI-1		E-143
STA. 324+10 LT	STOP MAIN ST	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN.		E-143
	1000 1206 0615	1	6	10	0.42						1					X																	MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-138
STA. 324+65 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X																	VR-017		E-141
STA. 325+40 RT	W3-1A	1	36	36	9.00						2					X																	W3-1A		E-150
STA. 63+06 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X																	VR-017		E-141
STA. 63+75 RT	STOP TH 6 COBB HILL RD	1	30	30	6.25		2				1					X																	RI-1 MOUNT STREET SIGNS OVER STOP SIGN.		E-143
STA. 64+45 RT	STOP 0020 1212 0008	1 1	36 6	36 10	9.00 0.42						2					X																	RI-1 MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN.		E-143 E-138
	SHEET 29 TOTAL				67.18		4									165																			
	SHEET 30 TOTAL				51.68		4									135																			
	SHEET 31 TOTAL				70.68		2									195																			
	SHEET 32 TOTAL				59.26		4									165																			
	SUB TOTAL				248.80		14					FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB							
	ROUNDING				16.20		-									20																			
					SF 265	SF	EA. 14	SF				FT			FT 680					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 4

PROJECT NAME: MORETOWN-DUXBURY-MORETOWN
PROJECT NUMBER: STP 2507 (I)S

FILE NAME: p05b050.DGN
PROJECT LEADER: EPD
DESIGNED BY: CDL
PLOT FILE: p05b050tss4.DGN

PLOT DATE: 31-OCT-2012 16:10
DRAWN BY: RHB
CHECKED BY: EPD
SHEET 32 OF 33