STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD. lb/ft 1.7	FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
ST. GEORGE 13+90 RT	ONLY	1	30	30	6.25						1					X																		VR-921		E-145A
30+15 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1					X																		REFER TO STANDARD E-121 FOR PLACEMENT. VR-017		E-141
30+45 RT	STOP 1160 0412 0059	1	30	30	6.25		1				1					X																		R1-1		E-143
SHELBURNE 1+55 LT	STOP 1160 0413 0003	1	30	30	6.25		1				1					X																		BACK TO BACK R1-1		E-143
1+85 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1					X																		REFER TO STANDARD E-121 FOR PLACEMENT. VR-017		E-141
74+00 LT	1160 0413 0140						1																										1R		
ST. GEORGE 79+90 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1					X																		REFER TO STANDARD E-121 FOR PLACEMENT. VR-017		E-141
80+05 RT	STOP 1160 0412 0150	1	30	30	6.25		1				1					X																		BACK TO BACK R1-1		E-143
82+70 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1					X																		REFER TO STANDARD E-121 FOR PLACEMENT. VR-017		E-141
83+70 RT	STOP	1	30	30	6.25						1					X																		R1-1		E-143
21+94 LT		1	12	36	3.0						1					X																		OM-3R		E-120
21+94 RT		1	12	36	3.0						1					X																		OM-3L		E-120
SO. BURLINGTON 0+08 LT		1	12	36	3.0						1					X																		OM-3L		E-120
0+08 RT		1	12	36	3.0						1					X																		OM-3R		E-120
			SF	SF	EA.	SF			FT	FT	FT	FT	FT 195	FT		EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB								
	SHEET TOTALS		63.25		3								195																							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEET AND THE ROADWAY, TRAFFIC & SAFETY AND PAVEMENT MANAGEMENT SECTION'S SIGN POST DESIGN GUIDELINE.

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT: **ST. GEORGE–SO. BURLINGTON**
PROJECT NO.: **ST-STP 2508(1)S**
DATE: 8-06

DESIGN FILE NAME: p05b052.dgn
IPARM FILE NAME: p05b052ts01.i
SURVEYED BY:
SQUAD LEADER:

PLOT DATE: 03-MAY-2012 17:55
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **30** OF **42**