STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																			REMARKS	SIGN DETAIL	
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			FOUNDATION	TUBULAR STEEL Ø (in) lb/ft				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAMED REQUIRED		DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
															1.75	2.0	2.5			3.0	4.0	4.0 MOD.		3.0	3.5	4.0	5.0	24"	30"						
												1.12	2.0	3.0	1.88	2.16	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
											OPTION ITEMS																								
162+15 LT	ONLY ONLY	1	48	30	10.0						2					X																VR-932		E-145B
165+00 RT	SO. BURLINGTON 1 / AIRPORT						2				2					X																RELOCATE EXISTING INFORMATION SIGNS.		
165+55 LT	STOP	1	30	30	6.25						1					X																R1-1		E-143
165+95 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	~~5.0~~						1					~~X~~																REFER TO STANDARD E-121 FOR PLACEMENT. VR-017		E-141
166+24 RT	W3-3	1	36	36	9.0						2					~~X~~																W3-3		E-152
167+00 LT	ONLY	1	30	30	6.25						1					X																VR-921		E-145A
180+00 LT	W3-3	1	36	36	9.0						~~2~~					~~X~~																POSTS OKAY (SQUARE TUBE) W3-3		E-152
	1160 0414 0340						~~1~~																											
187+15 LT	STOP 1160 0414 0354	1	30	30	6.25		1				1					~~X~~																POSTS OKAY (SQUARE TUBE) BACK TO BACK R1-1		E-143
187+50 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1					~~X~~																REFER TO STANDARD E-121 FOR PLACEMENT. VR-017 POSTS OKAY (SQUARE TUBE)		E-141
189+65 LT	STOP 1160 0414 0359	1	30	30	6.25		1				1					X																BACK TO BACK R1-1 USED EXISTING STUB		E-143
189+95 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	~~5.0~~						1					~~X~~																REFER TO STANDARD E-121 FOR PLACEMENT. VR-017 NEW SIGN AND POST EXIST		E-141
			SF	SF	EA.	SF			FT	FT	FT	FT	FT 226	FT		EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB							
	SHEET TOTALS		68.0		5								226																					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEET AND THE ROADWAY. TRAFFIC & SAFETY AND PAVEMENT MANAGEMENT SECTION'S SIGN POST DESIGN GUIDELINE.

TRAFFIC SIGN SUMMARY SHEET #6

PROJECT: **ST. GEORGE-SO. BURLINGTON**
PROJECT NO.: **ST-STP 2508(1)S**
DATE: 8-06

DESIGN FILE NAME: p05b052.dgn
IPARM FILE NAME: p05b052ts06.i
SURVEYED BY:
SQUAD LEADER:

PLOT DATE: 03-MAY-2012 17:55
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **35** OF **42**