

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS				DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES				
									FULL E&C	EROSION CONTROL	ROADWAY	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
										1				1		TON	HAYMULCH	651.25			
										10	170			180		CY	TOPSOIL	651.35			
												100		100		SY	GRUBBING MATERIAL	651.40			
										1				1		LS	EPSC PLAN	652.10			
										15				15		HR	MONITORING EPSC PLAN	652.20			
										1				1		LU	MAINTENANCE OF EPSC PLAN (N. A. B. I.)	652.30			
										140				140		SY	TEMPORARY EROSION MATTING	653.20			
										10				10		CY	VEHICLE TRACKING PAD	653.35			
										2265				2265		LF	PROJECT DEMARCATION FENCE	653.55			
											2			2		EACH	ERECTING SALVAGED SIGNS	675.60			
											1			1		EACH	SETTING SALVAGED POSTS	675.61			
												40		40		CY	SPECIAL PROVISION (STONE FILL, CULVERT LINING)	900.608			
												10		10		GAL	SPECIAL PROVISION (WATER REPELLENT, SILANE)	900.625			
												200		200		LF	SPECIAL PROVISION (HD STEEL BEAM GUARDRAIL, GALVANIZED / NESTED)	900.640			
											1056			1056		LF	SPECIAL PROVISION (MAINTENANCE AND REMOVAL OF TEMPORARY TRAFFIC BARRIER)	900.640			
												1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645			