STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												1.3	1.7	1.7	1.88	2.16	3.35			7.6	9.0	10.8	14.6												
												OPTION ITEMS																							
ROCHESTER: 336+00.0, RT		1	12	36	3.00						1			X		X		X															SIGN ID CODE OM-3R		E-107
336+40.0, LT		1	12	36	3.00						1			X		X		X															SIGN ID CODE OM-3R		E-107
340+52.0 RT	SPEED LIMIT 30	1	24	30	5.0																														
336+40.0, RT		1	12	36	3.00						1			X		X		X															SIGN ID CODE OM-3L		E-107
340+96.0 RT	0730 1415 0650	1	6	10	0.42																														
385+64.0 LT ~~340+96.0 RT~~	MAPLE HILL ~~0730~~ 1415 0650		1	6	10	0.42	1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL SALVAGING TO THE SIGN POST.	-	-
	STOP ~~0730~~ ~~1405~~ 1415 0731	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
385+52.0 LT	STOP	1	30	30	6.25																														
396+73.0, LT	AUSTIN HILL						1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP ~~0730~~ ~~1405~~ 1415 0752	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
397+08.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X		X															SIGN ID CODE VR-014		E-141
438+67.0, LT	CLAY HILL						1																										SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	0730 1415 0836	1	6	10	0.42																														
												LF	LF	LF 84	LF	LF 84	LF		EA	LB	LB	LB		LB	LB	LB	LB								
		TOTALS			SF ~~27.34~~ 39.43	SF	EA. 3	SF				LF 84			LF 84					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: ROCHESTER-CHITTENDEN-ROCHESTER
PROJECT NUMBER: STP 2505(1)S

FILE NAME: p05c046.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p05c046tss02.i
PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 44 OF 56