

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	EROSION CONTROL	UTILITIES	BRIDGE	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						50					50		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
									250		250		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							40				40		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							40				40		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							10				10		LB	SEED	651.15				
							20				20		LB	SEED-WINTER RYE	651.17				
							100				100		LB	FERTILIZER	651.18				
							1				1		TON	AGRICULTURAL LIMESTONE	651.20				
							1				1		TON	HAYMULCH	651.25				
						40	10				50		CY	TOPSOIL	651.35				
									200		200		SY	GRUBBING MATERIAL	651.40				
							1				1		LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10				
							40				40		HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20				
							1				1		LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30				
							350				350		SY	EROSION MATTING	654.10				
						5.75					5.75		SF	TRAFFIC SIGNS, TYPE A	675.20				
						47.75					47.75		LF	FLANGED CHANNEL SIGN POST	675.301				
						6					6		EACH	REMOVING SIGNS	675.50				
						4					4		EACH	ERECTING SALVAGED SIGNS	675.60				

PROJECT NAME: **WHITINGHAM**  
PROJECT NUMBER: **ST CULV(6)**  
FILE NAME: 05c128/Str/s05c128excel.dgn PLOT DATE: 02/23/2006  
PROJECT MANAGER: C.P.WILLIAMS DRAWN BY: E.L.RUSTAY  
DESIGNED BY: E.L.RUSTAY CHECKED BY: M.GAGULIC  
**QUANTITY SHEET #2** SHEET 4 OF 34