STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B" REMOVE 675.50	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 / 1.88	SQUARE STEEL (in) lb/ft 2.0 / 2.16	SQUARE STEEL (in) lb/ft 2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 / 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 / 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD. / 1.7	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 / 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 / 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 / 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 / 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
310+85 LT	STOP	1	30	30	6.25						1			X 14		X																			E-143
311+43 LT	YIELD	1	36 X 36 X 36		7.80	1					1			X 14		X																			E-146
ADDED 312+00 RT	NORTH 7					2	2							12																						
311+57 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0	1					1			X 14		X																		REFER TO STANDARD E-121 FOR PLACEMENT.		E-141
333+05 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1			X 14		X																		REFER TO STANDARD E-121 FOR PLACEMENT.		E-141
	EDGEWATER TER					1	1																													
333+45 RT	STOP 0070 0410 0631	1	30	30	6.25	1	1				1			X 14		X																		BACK TO BACK		E-143
18+85	WARNING UNDER GROUND					1																														
GEORGIA 18+45 LT	STOP 0070 0608 0035	1	30	30	6.25	2	1				1			X 14		X																		BACK TO BACK		E-143
18+85 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0	1					1			X 14		X																		REFER TO STANDARD E-121 FOR PLACEMENT.		E-141
22+25 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0	1					1			X 16		X																		REFER TO STANDARD E-121 FOR PLACEMENT.		E-141
	SPEED LIMIT 25					1	1																														
22+25	WARNING					1																														
22+70 RT	STOP 0070 0608 0042	1	30	30	6.25	2	1				1			X 14		X																		BACK TO BACK		E-143
			SF	SF	EA.	SF			LF	LF	LF 135	LF	LF 135	LF		EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB							
	SHEET TOTALS		52.80	15	7 ~~5~~				~~140~~ 135				135																							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

TRAFFIC SIGN SUMMARY SHEET #8

PROJECT: **MILTON – GEORGIA**
PROJECT NO.: **STP 2510(1)S**
DATE: 8-06

DESIGN FILE NAME: 05cl58.dgn
IPARM FILE NAME: 05cl58ts8.i
SURVEYED BY:
SQUAD LEADER:

PLOT DATE: 19-MAY-2009 12:23
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **41** OF **44**