QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

FULL E&C	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	120	120	CY	COMMON EXCAVATION	203.15	3.89
	1	1	CY	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.20	EST
	22,500	22,500	SY	COLD PLANING - BIT. PAVEMENT	210.10	403
	110	110	TON	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	11.22
	120	120	CWT	EMULSIFIED ASPHALT	404.65	10
	2,550	2,550	TON	SUPERPAVE BIT. CONCRETE PAVEMENT (PG 64-28)	490.30	92
	50	50	LF	BRIDGE EXPANSION JOINT - (ASPHALTIC PLUG) (MOD. - BUTT JOINT)	516.10	
	43	43	EA	REHABING DI,CB OR MH CLASS I	604.412	EST
	29	29	EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42	EST
	30	30	HR	POWER BROOM RENTAL , TYPE II	608.31	EST
	25	25	HR	TRUCK RENTAL	608.37	EST
	300	300	LF	VERTICAL GRANITE CURB	616.21	28
	300	300	LF	REMOVAL OF EXISTING CURB	616.41	28
	300	300	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5'' (MOD.)	618.10	30.10
	22	22	SY	DETECTABLE WARNING SURFACE	618.30	0.66
	40	40	EA	ADJUST ELEVATION OF VALVE BOX	629.20	EST
	300	300	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
	500	500	HR	FLAGGERS	630.15	EST
1		1	LS	FIELD OFFICE - ENGINEERS	631.10	-
1		1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
1		1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
1		1	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-
	1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
	1	1	LS	TRAFFIC CONTROL	641.10	-
	1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-
	4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
	7500	7500	LF	DURABLE 4'' WHITE LINE (TYPE I, TAPE)	646.40	70
	7600	7600	LF	DURABLE 4'' YELLOW LINE (TYPE I, TAPE)	646.41	70
	75	75	LF	DURABLE 8'' YELLOW LINE (TYPE I, TAPE)	646.43	5

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SUPERPAVE BIT. CONCRETE PAVEMENT (PG 64-28)
826	T	LEVELING (TYPE IV) (MAINLINE)
1,376	T	WEARING (TYPE IV) (MAINLINE)
96	T	LEVELING (TYPE IV) (SIDEROADS)
160	T	WEARING (TYPE IV) (SIDEROADS)
92	T	ROUNDING
2,550	T	GRAND TOTAL
		COLD PLANING - BIT. PAVEMENT
19,813	SY	MAINLINE
2,284	SY	SIDEROADS
403	SY	ROUNDING
22,500	SY	GRAND TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

/pave /05d144 /p05d144.dgn
p05d144qs01.i

PROJECT NAME **WINOOSKI**
PROJECT NUMBER **STP 2306(1)S**