STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
17+43.5 RT	MAIN ST		30	12	2.5																													22	
	STOP / PART ST		30 36	30 12	6.25 3						1			X 14		X																	USE MOUNTING BRACKET AS SHOWN ON E-160	22	E-143
19+23 RT	ONLY		36	30	7.5						2			X 14,14		X																			E-145A
20+80 LT	ONLY		36	30	7.5						2			X 14,14		X																	ASSEMBLY ON WEST SPRING STREET		E-145A
21+21 RT	ONLY		36	30	7.5						2			X 14		X																	ASSEMBLY ON EAST SPRING STREET		E-145A
22+64 LT	ONLY		36	30	7.5						2			X 14,14		X																			E-145A
28+13 LT	MAIN ST		30	12	2.5																													22	
	STOP / STEVENS ST		30 42	30 12	6.25 3.5						1			X 14		X																	USE MOUNTING BRACKET AS SHOWN ON E-160	22	E-143
28+27 RT							1				1			X 12		X																			
												FT	FT	FT 102	FT	FT 102	FT		EA	LB	LB	LB		LB	LB	LB	LB								
											TOTALS	SF 54	SF	EA. 1	SF		FT 102		FT 102		LB		EA.		LB			EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: **WINOOSKI**
PROJECT NUMBER: **STP 2306(1)S**

FILE NAME: **/pave /05d144/p05d144.dgn**
PROJECT LEADER: **WOOLAVER**
IPARM NAME: **p05d144tss02.i**

PLOT DATE: 18-JAN-2008 11:44
DRAWN BY: **WILDER**
CHECKED BY: **PAVT MGMT**
SHEET 15 OF 23 _____