STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES																	TOTALS			DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
											EROSION		E & C		ROADWAY	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
															2139			2139		CY	COMMON EXCAVATION	203.15			
															183			183		CY	EARTH BORROW	203.30			
															308		42	350		CY	TRENCH EXCAVATION OF EARTH	204.20			
															53		47	100		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30			
															155		45	200		SY	COLD PLANING - BIT. PAVEMENT	210.10			
															1810		90	1900		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35			
															4			4		CWT	EMULSIFIED ASPHALT	404.65			
															960		10	970		TON	BITUMINOUS CONCRETE PAVEMENT	406.25			
															14			14		CY	CONCRETE, CLASS B	501.25			
															1201			1201		LB	REINFORCING STEEL	507.15			
															240			240		LF	18" CPEP (SL)	601.2615			
															79			79		LF	24" CPEP (SL)	601.2620			
															1			1		EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42			
											30						10	40		CY	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	613.10			
											10						10	20		CY	STONE FILL, TYPE I (MOD. - INLET PROTECTION)	613.10			
											14						6	20		CY	STONE FILL TYPE II	613.11			
															100		10	110		LF	GRANITE SLOPE EDGING	616.20			
															360		10	370		LF	CAST-IN PLACE CONCRETE CURB, TYPE B	616.28			
															124		1	125		LF	REMOVAL OF EXISTING CURB	616.41			
															8		2	10		EA	YIELDING MARKER POSTS	619.17			
															1954		1	1955		LF	SNOW FENCE (MOD. - PDF)	620.70			
															42			42		LF	STEEL BEAM GUARD RAIL	621.20			
															2			2		EA	ANCHOR FOR STEEL BEAM RAIL	621.60			
															120			120		HR	UNIFORMED TRAFFIC OFFICERS	630.10			
															360			360		HR	FLAGGERS	630.15			
													1					1		LS	TESTING EQUIPMENT - CONCRETE	631.16			
													1					1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17			
															1			1		LS	MOBILIZATION/DEMOBLILIZATION	635.11			
															1			1		LS	TRAFFIC CONTROL	641.10			
															1850		10	1860		LF	4" WHITE LINE	646.20			
															1730		10	1740		LF	4" YELLOW LINE	646.21			
															34		1	35		LF	24" STOP BAR	646.26			
															13			13		EA	LETTER OR SYMBOL	646.30			
															3735		5	3740		SY	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR	649.11			
											293						2	295		SY	GEOTEXTILE FOR SILT FENCE	649.51			
											12						38	50		LB	SEED	651.15			
											97						3	100		LB	FERTILIZER	651.18			
											0.39						0.61	1		TON	AGRICULTURAL LIMESTONE	651.20			
											0.39						0.61	1		TON	HAY MULCH	651.25			
											53						22	75		CY	TOPSOIL	651.35			

PROJECT NAME: **BARRE TOWN**
PROJECT NUMBER: **ST 0147(16)**

FILE NAME: **D05E290/Design/05E290FRM**
PROJECT MANAGER: **R. THOMPSON**
DESIGNED BY: **P. PELOQUIN**
05e290qty1.i

PLOT DATE: **8/14/2006**
DRAWN BY: **P. PELOQUIN**
CHECKED BY: