

QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	ROADWAY (STAGE ONE SITES)	TRAINING	LANDSCAPING	EROSION CONTROL	UTILITIES	FURNACE BROOK BRIDGE	EAST ROAD + SUP BRIDGE	FULL C.E. ITEMS		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					10					10		M	SEAMLESS COPPER WATER TUBE (25 MM)	629.23	1			
					5					5		M	DUCTILE IRON PIPE, CEMENT-LINED (150 MM)	629.24	-			
					5					5		M	DUCTILE IRON PIPE, CEMENT-LINED (200 MM)	629.24	-			
	10									10		M	DUCTILE IRON PIPE, CEMENT-LINED (300 MM)	629.24	-			
					181					181		M	DUCTILE IRON PIPE, CEMENT-LINED (400 MM)	629.24	-			
					2					2		EACH	EXTENSION SERVICE BOX AND CURB STOP (25 MM)	629.25	-			
					1					1		EACH	GATE VALVE WITH VALVE BOX (150 MM)	629.27	-			
					1					1		EACH	GATE VALVE WITH VALVE BOX (200 MM)	629.27	-			
	1									1		EACH	GATE VALVE WITH VALVE BOX (300 MM)	629.27	-			
					4					4		EACH	GATE VALVE WITH VALVE BOX (400 MM)	629.27	-			
					1					1		EACH	HYDRANT	629.28	-			
					1					1		EACH	REMOVE HYDRANT	629.30	-			
					2					2		EACH	CORPORATION STOP (25 MM)	629.39	-			
					1					1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM	629.42	-			
	1100	250								1350		HR	UNIFORMED TRAFFIC OFFICERS	630.10	13.2			
	14950	7500								22450		HR	FLAGGERS	630.15	21			
										1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
			1560							1560		HR	EMPLOYEE TRAINEESHIP	634.10	-			
	1									1		LS	MOBILIZATION/DEMOLITION	635.11	-			
	1									1		LS	TRAFFIC CONTROL	641.10	-			
	1									1		LS	PUBLIC RELATIONS OFFICER	641.12	-			
	4	2								6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
	840									840		M	DURABLE 100 MM WHITE LINE, THERMOPLASTIC	646.402	10			
	810	520								1330		M	DURABLE 100 MM YELLOW LINE, THERMOPLASTIC	646.412	4			
	1500									1500		M	DURABLE 150 MM WHITE LINE, THERMOPLASTIC	646.422	5			
	1460									1460		M	DURABLE 150 MM YELLOW LINE, THERMOPLASTIC	646.432	5			
	5									5		M	DURABLE 600 MM STOP BAR, THERMOPLASTIC	646.482	0.5			
	4									4		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-			
	1680									1680		M	TEMPORARY 100 MM WHITE LINE, PAINT	646.602	20			
	1620									1620		M	TEMPORARY 100 MM YELLOW LINE, PAINT	646.612	8			
	3440									3440		M	TEMPORARY 150 MM WHITE LINE, PAINT	646.622	10			
	3280									3280		M	TEMPORARY 150 MM YELLOW LINE, PAINT	646.632	10			
	10									10		M	TEMPORARY 600 MM STOP BAR, PAINT	646.682	1			
	8									8		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
	584	25								609		EACH	LINE STRIPING TARGETS	646.76	-			
	20									20		SM	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	0.5			
	26810									26810		SM	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	4			
	5317	280				7445	218			13260		SM	GEOTEXTILE UNDER STONE FILL	649.31	4			
		6000			1585					7585		SM	GEOTEXTILE FOR SILT FENCE	649.51	0.1			

PROJECT NAME:	BENNINGTON		
PROJECT NUMBER:	AC NH 019-1(53)		
FILE NAME:	ZD307C3VAOT_QUANT.XLS	PLOT DATE:	5/17/2007
PROJECT LEADER:	G.SANTY	DRAWN BY:	STANTEC
DESIGNED BY:	M. FOISY	CHECKED BY:	G. SANTY
QUANTITY SHEET #5		SHEET	16 OF 577

V:\953\active\953\002\transportation\drawing\contract\3\plot_files\z307c3\vaot_quant07.pdf