STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH	HEIGHT	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø FOUND-ATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600	750	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
OPTION ITEMS																																				
RAMP G I+358 G ~~I+020.0~~, RT.	RAMP 25 M.P.H.	1	900	1200	1.08						2			9.45 ~~9.2~~																					W13-3		E-150
SEE SHEET SP-04 FOR LOCATIONS		15 ~~11~~	750	900	10.13 ~~7.43~~						15 ~~11~~			63.4 ~~50.6~~																					W1-8		E-150
C I+685 ~~G I+637.8~~, LT.	ONE WAY	1	900	300	0.27						2			7.32 ~~9.2~~																							
G I+660.8, RT.		1	900	900	0.81						2 ~~1~~			8.84 ~~4.6~~																					R3-2		E-143
I+798 G ~~I+789.8~~, RT.	TO NORTH 7	1 1 1 1	750 750 900 600	375 375 900 450	0.28 0.28 0.81 0.27						2 ~~1~~			10.7 ~~4.6~~																							
EAST ROAD ER I+027.6, LT.	R1-1 THIS SIGN ON STREET	1	300	450	0.14						1			4.6																						TSD-01	
ER I+046.4, RT.	EAST RD STOP SIGNALS AHD	1	750	750	0.56		1 1				1			4.6																					MOUNT NEW STOP SIGN WITH SALVAGED STREET SIGNS. INSTALL SALVAGED STREET SIGNS 90° TO EACH OTHER, 150 ABOVE THE STOP SIGN USING POST TOP MOUNTING BRACKET ON A NEW POST. R1-1	- -	- E-143
ER I+120.9, LT.	SPEED LIMIT 35	1	600	750	0.45						1			4.6																					R2-1		E-142
ER I+121.2, RT.	SPEED LIMIT 35	1	600	750	0.45						1			4.6																					R2-1		E-142
EXIT 2 RAMP A A I+013.2, RT.	EXIT 35 M.P.H.	1	900	1200	1.08						2			9.3 ~~9.2~~																					W13-2		E-150
A I+067.1, LT.		1	450	450	0.20						1			3.8 ~~4.6~~																					OM-1		E-150
A I+071.4, LT.	EXIT 2	1	1800	1500		2.70					~~2~~ 0			~~9.2~~ 0	INSTALLED ON EXISTING POSTS																					E5-1a		E-131
												m	m	m	m	m	m	EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS			m² 14.11	m² 2.70	EA. 2	m²						m 119.6			m				kg	EA.	kg						EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BENNINGTON
PROJECT NUMBER: AC NH 019-1(53)

FILE NAME: tsss.dgn
PROJECT LEADER: GREG EDWARDS
DESIGNED BY: MARC FOISY
PLOT DATE: 5/25/2011
DRAWN BY: STANTEC
CHECKED BY: GARY SANTY

TRAFFIC SIGN SUMMARY TSS-01