# STATE OF VERMONT
# AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

| KILOMETER MARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH | HEIGHT | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | EXIST POST SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL kg/m 1.7 | 3.0 | 4.5 | SQUARE STEEL 44 kg/m 3.4 | 50 kg/m 3.9 | 63 kg/m 5.0 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø 75 kg/m 1.9 | 100 kg/m 2.5 | 100 MOD kg/m 2.5 | TUBULAR STEEL Ø FOUNDATION | 75 kg/m 11.3 | 89 kg/m 13.4 | 100 kg/m 16.1 | 125 kg/m 21.7 | W-SHAPE STEEL FTG. SIZE 600 | 750 | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A 1+110.2, RT.<br>B 0+954, RT. | | 2<br>~~1~~ | 900 | 900 | 1.62<br>~~0.81~~ | | | | | | 4<br>~~1~~ | | | | | | 17.16<br>~~4.6~~ | | | | | | | | | | | | | | | | | | WI1-3 | TSD-01 | |
| A 1+308.3, RT. | <br> | 1<br>1 | 900<br>600 | 900<br>600 | 0.81<br>0.36 | | | | | | 2<br>~~1~~ | | | | | | 9.46<br>~~4.6~~ | | | | | | | | | | | | | | | | | | WI-2L<br>WI3-1 | | E-151<br>E-155 |
| EXIT 2<br>RAMP B<br>B 0+924.0, RT. | <br> | 1<br>1 | 900<br>600 | 900<br>600 | 0.81<br>0.36 | | | | | | 2<br>~~1~~ | | | | | | 9.54<br>~~4.6~~ | | | | | | | | | | | | | | | | | | WI-2R<br>WI3-1 | | E-151<br>E-155 |
| ~~B 0+954.0, RT.~~ | | ~~1~~ | ~~900~~ | ~~900~~ | ~~0.81~~ | SEE ABOVE | | | | | ~~1~~ | | | | | | ~~4.6~~ | | | | | | | | | | | | | | | | | | WI1-3 | TSD-01 | |
| B 1+464.9, RT. | | 1 | 900 | 900 | 0.81 | | | | | | 2<br>~~1~~ | | | | | | 9.28<br>~~4.6~~ | | | | | | | | | | | | | | | | | | R3-2 | | E-143 |
| | SHT. TSS-02 TOTALS | | | | 4.77 | | | | | | | | | | | | 23.0 | | | | | | | | | | | | | | | | | | | | |
| | SHT. TSS-01 TOTALS | | | | 14.11 | 2.70 | 2 | | | | | | | | | | 119.6 | | | | | | | | | | | | | | | | | | | | |
| | SUB TOTALS | | | | 18.88 | 2.70 | 2 | | | | | | | | | | 142.6 | | | | | | | | | | | | | | | | | | | | |
| | ROUNDING | | | | 0 | 0 | 0 | | | | | | | | | | 0 | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | m | m | m | m | m | m | EA | kg | kg | kg | | kg | kg | kg | kg | | | | | | | | | | |
| **TOTALS** | | | | | m² 18.88 | m² 2.70 | EA. 2 | m² | | | | m 142.6 | | | m | | | | kg | | | EA. | kg | | | | EA. | EA. | kg | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BENNINGTON
PROJECT NUMBER: AC NH 019-1(53)

FILE NAME: tsss.dgn
PROJECT LEADER: GREG EDWARDS
DESIGNED BY: MARC FOISY
**TRAFFIC SIGN SUMMARY TSS-02**

PLOT DATE: 5/25/2011
DRAWN BY: STANTEC
CHECKED BY: GARY SANTY
SHEET 153 OF 577