

		FULL CE	ROADWAY	TOTAL QUANTITY	UNIT	DESCRIPTION	ITEM	ROUNDING
		1		1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
		1		1	LU	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.25	-
			1	1	LS	MOBILIZATION/DEMobilIZATION	635.11	-
			1	1	LS	TRAFFIC CONTROL	641.10	-
			3	3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			99,000	99,000	LF	4 INCH WHITE LINE	646.20	EST.
			92,000	92,000	LF	4 INCH YELLOW LINE	646.21	EST.
			120	120	LF	24 INCH WHITE LINE	646.26	EST.
			48	48	EA	LETTER OR SYMBOL	646.30	EST.
			99,000	99,000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.
			92,000	92,000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.
			120	120	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.
			48	48	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.
			1,000	1,000	EA	LINE STRIPING TARGETS	646.76	EST.
			3,250	3,250	SY	GEOTEXTILE UNDER STONE FILL	649.31	EST.
			30	30	LB	SEED	651.15	EST.
			250	250	LB	FERTILIZER	651.18	EST.
			1	1	TON	AGRICULTURE LIMESTONE	651.20	EST.
			8,700	8,700	SY	TEMPORARY EROSION MATTING	653.20	EST.
			525	525	SF	TRAFFIC SIGNS, TYPE A	675.20	EST.
			143	143	SF	TRAFFIC SIGNS, TYPE B	675.21	EST.
			1,000	1,000	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	EST.
			123	123	EA	REMOVING SIGNS	675.50	EST.
			2	2	EA	ERECTING SALVAGED SIGNS	675.60	EST.
			47	47	EA	DELINEATORS WITH STEEL POSTS	676.10	EST.
			47	47	EA	REMOVAL OF EXISTING DELINEATORS	676.12	EST.
			1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
			1,050	1,050	SY	SPECIAL PROVISION (HAND PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	43

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
COLD PLANING-BIT. PAVEMENT		
117,000	SY	MAINLINE
1,913	SY	TH'S AND PULLOUTS
118,913	SY	SUBTOTAL
1,087	SY	ROUNDING
120,000	SY	GRAND TOTAL
SUPERPAVE BITUMINOUS CONCRETE PAVEMENT		

400	TON	PULLOUT (WOODFORD) - TYPE II
3,216	TON	LEVELING - TYPE IV
9,649	TON	WEARING COURSE - TYPE IV
627	TON	TH'S AND PULLOUTS - TYPE IV
13,892	TON	SUBTOTAL
208	TON	ROUNDING
14,100	TON	TOTAL

QUANTITY SHEET #2

PROJECT NAME:	WOODFORD - SEARSBURG
PROJECT NUMBER:	NH ST 2630 (I)
FILE NAME: p06b228.dgn	PLOT DATE: 04-OCT-2011 12:47
PROJECT LEADER: TED DOMEY	DRAWN BY: WILDER
DESIGNED BY: HUNT	CHECKED BY: PAVT MGMT
IPARM FILE NAME: 06b228qs2.i	SHEET 6 OF 24